PROPOSED STORM SEWER SCHEDULE

LOCATION	STRUCT. TO STRUCT.	UP RIM ELEV.	UP INV. ELEV.	DN RIM ELEV.	DN INV. ELEV.	LENGTH (FT)	SLOPE %	STORM SEWERS, CLASS A, TYPE 1, 12" (FT)	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12" (FT)	STORM SEWERS, CLASS A, TYPE 1, 15" (FT)	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 15" (FT)	STORM SEWERS, CLASS A, TYPE 1, 21" (FT)	STORM SEWERS, CLASS A, TYPE 1, 24" (FT)	STORM SEWERS, CLASS A, TYPE 1, 30" (FT)	STORM SEWERS, CLASS A, TYPE 1, 36" (FT)	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 8" (FT)	STORM SEWERS, CLASS A, TYPE 2, 4" (FT)	STORM SEWERS, CLASS A, TYPE 2, 12" (FT)	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12" (FT)	STORM SEWERS, CLASS A, TYPE 2, 15" (FT)	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 15" (FT)	STORM SEWERS, CLASS A, TYPE 2, 18" (FT)
STA. 270+10.00, 34.5' LT TO STA. 269+27.00, 33.4' LT	137 TO 136	800.99	797.49	801.19	797.08	82.9	0.50	82.9														
STA. 269+27.00, 33.4' LT TO STA. 269+27.00, 80' LT	136 TO 148	801.19	792.86	792.52	792.52	45.3	1.20															
STA. 260+00.00, 30' RT TO STA. 258+50.00, 30' RT	138 TO 86	802.08	798.18	799.28	794.42	150.5	2.50												150.5			
STA. 263+78.20, 31.24' RT TO STA. 264+70.00, 32.82' RT	139 TO 140	803.03	799.53	802.65	799.07	91.8	0.50	91.8														
STA. 264+70.00, 32.82' RT TO STA. 265+60.00, 34.37' RT	140 TO 141	802.65	798.87	802.38	798.42	90.0	0.50	90.0														
STA. 265+60.00, 34.37' RT TO STA. 266+50.00, 34.79' RT	141 TO 142	802.38	798.22	802.11	797.77	90.0	0.50											90.0				
STA. 266+50.00, 34.79' RT TO STA. 267+40.00, 34.43' RT	142 TO 143	802.11	797.57	801.84	797.12	90.0	0.50													90.0		
STA. 267+40.00, 34.43' RT TO STA. 268+30.00, 36.3' RT	143 TO 144	801.84	796.92	801.57	796.47	90.0	0.50													90.0		
STA. 268+30.00, 36.3' RT TO STA. 269+29.00, 43.23' RT	144 TO 145	801.57	796.27	801.08	795.77	99.2	0.50													99.2		
STA. 270+90.00, 47.19' RT TO STA. 270+10.00, 46.66' RT	147 TO 146	800.61	797.11	800.85	796.71	80.0	0.50	80.0														
STA. 270+10.00, 46.66' RT TO STA. 269+29.00, 43.23' RT	146 TO 145	800.85	796.51	801.08	796.10	81.2	0.50											81.2				
							TOTALS	1,055.0	131.4	302.7	72.5	203.1	193.2	1,201.8	521.4	105.0	25.9	530.1	629.8	1,031.2	740.5	171.0

PROPOSED STORM SEWER SCHEDULE

LOCATION	STRUCT. TO STRUCT.	UP RIM ELEV.	UP INV. ELEV.	DN RIM ELEV.	DN INV. ELEV.	LENGTH (FT)	SLOPE %	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 18" (FT)	STORM SEWERS, CLASS A, TYPE 2, 21" (FT)	STORM SEWERS, CLASS A, TYPE 2, 24" (FT)	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24" (FT)	STORM SEWERS, CLASS A, TYPE 2, 27" (FT)	STORM SEWERS, CLASS A, TYPE 2, 30" (FT)	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 30" (FT)	STORM SEWERS, CLASS A, TYPE 2, 36" (FT)	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 36" (FT)	STORM SEWERS, CLASS A, TYPE 2, 42" (FT)	STORM SEWERS, CLASS A, TYPE 2, 54" (FT)	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 54" (FT)	STORM SEWERS, TYPE 3, WATER MAIN QUALITY PIPE, 27" (FT)	STORM SEWERS, CLASS A, TYPE 3, 54" (FT)	CONTROLLED LOW-STRENGTH MATERIAL (CLSM) (CY)
STA. 203+25.68, 42' LT TO STA. 201+35.00, 36' LT	2 TO 1	716.69	701.70	716.61	699.80	190.1	1.00														190.1	619.0
STA. 204+91.00, 32.7' LT TO STA. 203+25.68, 42' LT	3 TO 2	717.89	703.45	716.69	701.80	165.0	1.00											165.0				473.8
STA. 206+00.00, 30' LT TO STA. 204+91.00, 32.7' LT	4 TO 3	718.46	704.64	717.89	703.55	109.0	1.00											109.0				293.2
STA. 208+00.00, 30' LT TO STA. 206+00.00, 30' LT	5 TO 4	718.17	706.75	718.46	704.74	200.0	1.00											200.0				443.7
STA. 208+96.45, 30' LT TO STA. 208+00.00, 30' LT	6 TO 5	718.08	707.81	718.17	706.85	96.5	1.00											96.5				160.7
STA. 209+60.00, 30' LT TO STA. 208+96.45, 30' LT	7 TO 6	718.12	710.34	718.08	710.02	63.6	0.50										63.6					57.3
STA. 210+50.00, 30' LT TO STA. 209+60.00, 30' LT	8 TO 7	718.32	710.99	718.12	710.54	90.0	0.50										90.0					69.9
STA. 211+90.00, 30' LT TO STA. 210+50.00, 30' LT	9 TO 8	718.94	711.89	718.32	711.19	140.0	0.50								140.0							102.4
STA. 213+30.00, 30' LT TO STA. 211+90.00, 30' LT	10 TO 9	719.96	713.43	718.94	712.17	140.0	0.90								140.0							87.2
STA. 215+20.09, 30' LT TO STA. 213+30.00, 30' LT	11 TO 10	721.87	715.15	719.96	713.63	190.1	0.80									190.1						112.5
STA. 216+00.00, 30' LT TO STA. 215+20.09, 30' LT	12 TO 11	722.72	715.91	721.87	715.35	79.9	0.70								79.9							50.1
STA. 218+00.00, 30' LT TO STA. 216+00.00, 30' LT	13 TO 12	725.41	719.11	722.72	716.11	200.0	1.50								200.0							114.9
STA. 220+00.00, 30' LT TO STA. 218+00.00, 30' LT	14 TO 13	729.78	724.31	725.41	719.31	200.0	2.50					200.0										67.1
STA. 222+00.00, 30' LT TO STA. 220+00.00, 30' LT	15 TO 14	735.55	729.51	729.78	724.51	199.9	2.50					199.9										62.7
STA. 224+29.79, 30' LT TO STA. 222+00.00, 30' LT	16 TO 15	742.34	736.56	735.55	729.71	228.3	3.00					228.3										77.3
STA. 225+50.00, 30' LT TO STA. 224+29.79, 30' LT	17 TO 16	745.89	738.55	742.34	736.76	119.4	1.50					119.4										76.2
STA. 227+81.11, 32' LT TO STA. 225+50.00, 30' LT	18 TO 17	752.52	741.05	745.89	738.75	229.6	1.00					229.6										286.4
STA. 228+85.50, 30' LT TO STA. 227+81.11, 32' LT	19 TO 18	755.63	742.29	752.52	741.25	103.7	1.00													103.7		196.1
STA. 231+00.00, 30' LT TO STA. 228+85.50, 30' LT	20 TO 19	760.29	754.37	755.63	750.75	213.1	1.70					213.1										58.6
STA. 233+00.00, 30' LT TO STA. 231+00.00, 30' LT	21 TO 20	763.49	757.55	760.29	754.57	198.7	1.50					198.7										68.0
STA. 235+00.00, 30' LT TO STA. 233+00.00, 30' LT	22 TO 21	766.36	760.73	763.49	757.75	198.8	1.50					198.8										63.4
STA. 237+30.00, 30' LT TO STA. 235+00.00, 30' LT	23 TO 22	769.85	763.92	766.36	760.93	230.0	1.30			230.0												75.8
STA. 239+50.00, 30' LT TO STA. 237+30.00, 30' LT	24 TO 23	773.18	767.42	769.85	764.12	220.0	1.50			220.0												74.7
STA. 241+00.00, 30' LT TO STA. 239+50.00, 30' LT	25 TO 24	775.44	769.87	773.18	767.62	150.0	1.50			150.0												47.0
STA. 242+00.00, 30' LT TO STA. 241+00.00, 30' LT	26 TO 25	776.84	771.57	775.44	770.07	100.0	1.50															27.7
STA. 243+00.00, 30' LT TO STA. 242+00.00, 30' LT	27 TO 26	778.13	772.77	776.84	771.77	100.0	1.00			100.0												26.1
STA. 244+60.00, 30' LT TO STA. 243+00.00, 30' LT	28 TO 27	779.94	774.57	778.13	772.97	160.0	1.00			160.0												34.8
STA. 245+30.00, 30' LT TO STA. 244+60.00, 30' LT	29 TO 28	780.67	775.47	779.94	774.77	70.0	1.00															25.6
STA. 246+55.00, 30' LT TO STA. 245+30.00, 30' LT	30 TO 29	781.96	776.92	780.67	775.67	125.0	1.00		125.0													30.8
STA. 248+00.00, 30' LT TO STA. 246+55.00, 30' LT	31 TO 30	783.46	778.57	781.96	777.12	145.0	1.00															32.5
STA. 249+85.00, 30' LT TO STA. 248+00.00, 30' LT	32 TO 31	785.37	779.88	783.46	778.77	185.0	0.60		185.0													47.3
STA. 251+21.71, 30' LT TO STA. 249+85.00, 30' LT	33 TO 32	786.82	780.90	785.37	780.08	136.7	0.60		136.7													44.5
STA. 252+40.80, 30' LT TO STA. 251+21.71, 30' LT	34 TO 33	788.28	783.24	786.82	781.10	119.1	1.80															35.6
STA. 254+00.00, 30' LT TO STA. 252+40.80, 30' LT	35 TO 34	790.60	786.31	788.28	783.44	159.2	1.80															32.6
STA. 256+00.00, 30' LT TO STA. 254+00.00, 30' LT	36 TO 35	794.07	790.11	790.60	786.51	200.0	1.80															28.3
STA. 258+00.00, 30' LT TO STA. 256+00.00, 30' LT	37 TO 36	798.17	794.70	794.07	790.31	199.5	2.20															19.2
STA. 202+61.08, 30' RT TO STA. 258+00.00, 30' LT	38 TO 39	716.73	713.61	717.71	712.64	193.5	0.50															30.6
STA. 204+54.00, 30' RT TO STA. 202+61.08, 30' RT	39 TO 40	717.71	712.44	718.44	711.19	250.1	0.50															107.7
STA. 207+04.01, 30' RT TO STA. 204+54.00, 30' RT	40 TO 41	718.44	710.99	718.17	710.51	96.0	0.50															80.1
STA. 208+00.00, 30' RT TO STA. 207+04.01, 30' RT	41 TO 42	718.17	710.31	718.08	709.83	96.5	0.50															88.8
STA. 208+96.45, 30' RT TO STA. 208+96.45, 30' LT	42 TO 6	718.08	708.35	718.08	707.91	62.5	0.70											62.5				87.6
STA. 209+60.00, 30' RT TO STA. 208+96.45, 30' RT	43 TO 42	718.12	708.90	718.08	708.45	63.6	0.70												63.6			78.7
STA. 210+50.00, 30' RT TO STA. 209+60.00, 30' RT	44 TO 43	718.32	709.63	718.12	709.00	90.0	0.70											90.0				96.8
STA. 211+90.00, 30' RT TO STA. 210+50.00, 30' RT	45 TO 44	718.94	710.71	718.32	709.73	140.0	0.70											140.0				128.9
STA. 213+30.00, 30' RT TO STA. 211+90.00, 30' RT	46 TO 45	719.96	711.79	718.94	710.81	140.0	0.70											140.0				117.5
STA. 215+22.59, 30' RT TO STA. 213+30.00, 30' RT	47 TO 46	721.90	713.24	719.96	711.89	192.6	0.70												192.6			174.6
STA. 216+00.00, 30' RT TO STA. 215+22.59, 30' RT	48 TO 47	722.72	713.88	721.90	713.34	77.4	0.70											77.4				78.2
STA. 217+40.00, 30' RT TO STA. 216+00.00, 30' RT	49 TO 48	724.44	714.96	722.72	713.98	140.0	0.70											140.0				159.4
STA. 218+70.00, 30' RT TO STA. 217+40.00, 30' RT	50 TO 49	726.75	720.41	724.44	718.46	130.0	1.50								130.0							57.8
STA. 220+80.00, 30' RT TO STA. 218+70.00, 30' RT	51 TO 50	732.00	725.86	726.75	720.61	210.0	2.50															89.4
STA. 222+40.00, 30' RT TO STA. 220+80.00, 30' RT	52 TO 51	736.73	730.55	732.00	726.06	160.4	2.80															55.4
STA. 223+90.00, 32.9' RT TO STA. 222+40.00, 30' RT	53 TO 52	741.10	734.98	736.73	730.75	151.0	2.80															50.7
STA. 224+40.00, 51' RT TO STA. 222+40.00, 30' RT	52A TO 52	735.00	732.00	736.73	731.00	15.0	0.66															1.8
STA. 225+00.00, 41.5' RT TO STA. 223+90.00, 32.9' RT	54 TO 53	744.19	737.45	741.10	735.23	111.2	2.00								111.2							59.8
STA. 226+15.00, 43' RT TO STA. 225+00.00, 41.5' RT	55 TO 54	747.56	740.90	744.19	737.65	116.0	2.80								116.0							70.9

CONTINUED ON FOLLOWING SHEET