

MAINTENANCE OF TRAFFIC SCHEDULE	AGGREGATE BASE COURSE, TYPE B 4"	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	AGGREGATE SHOULDERS, TYPE B	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING -				PAVEMENT MARKING TAPE, TYPE III					WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	PAVEMENT MARKING REMOVAL					
									LETTERS AND SYMBOLS	LINE 4"		LINE 8"	LINE 24"	LETTERS AND SYMBOLS	4"		8"					12"		24"		
										SQ FT	WHITE	YELLOW	FOOT		FOOT	SQ FT	WHITE					YELLOW	FOOT	FOOT	FOOT	FOOT
LOCATION	SQ YD	TON	TON	SQ YD	TON	SQ YD	TON	FOOT	WHITE	WHITE	YELLOW	WHITE	WHITE	WHITE	WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	SQ FT	FOOT	FOOT	SQ FT		
POST STAGE III								4159.66																		
STA 201+45.35 TO STA 270+78.11																					1386.41					
STA 194+00.00 TO STA 200+00.00																					869.89					
STA 200+00.00 TO STA 206+00.00																					1085.15					
STA 206+00.00 TO STA 212+00.00																					599.94					
STA 212+00.00 TO STA 218+00.00																					751.52					
STA 218+00.00 TO STA 224+00.00																					608.70					
STA 224+00.00 TO STA 230+00.00																					2804.35					
STA 230+00.00 TO STA 236+00.00																					626.34					
STA 236+00.00 TO STA 242+00.00																					599.94					
STA 242+00.00 TO STA 248+00.00																					599.94					
STA 248+00.00 TO STA 254+00.00																					599.94					
STA 254+00.00 TO STA 260+00.00																					599.35					
STA 260+00.00 TO STA 266+00.00																					599.97					
STA 266+00.00 TO STA 272+00.00																					310.87					
STA 272+00.00 TO STA 278+00.00																					357.93					
STA 278+00.00 TO STA 284+00.00																					130.28					
SUB-TOTAL	4460.79	0.02	1.15	145.34	48.13	427.63	51.06	5607.33	44.00	25647.35	431.87	117.46	193.60	35707.04	2481.13	140.00	252.08	348.51	17725.19	2675.00	2475.00	6892.19				
TOTAL	4461	0.1	1.2	146	49	428	52	5608	44	25648	432	118	194	35708	2482	392	349	17726	2675	2475	6893					

MAINTENANCE OF TRAFFIC SCHEDULE	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 2	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	TEMPORARY PAVEMENT	TEMPORARY PAVEMENT REMOVAL
LOCATION	EACH	EACH	SQ YD	SQ YD
PRE-STAGE A				
STA 200+00.00 TO STA 206+00.00			8.91	
STA 206+00.00 TO STA 212+00.00	2		637.20	
STA 212+00.00 TO STA 218+00.00				
PRE-STAGE B				
STA 200+00.00 TO STA 206+00.00			269.69	
STA 206+00.00 TO STA 212+00.00		2		355.34
STA 212+00.00 TO STA 218+00.00			308.44	
STA 218+00.00 TO STA 224+00.00			427.46	
STA 224+00.00 TO STA 230+00.00			241.45	
STAGE I				
STA 194+00.00 TO STA 200+00.00				
STA 200+00.00 TO STA 206+00.00		2		
STA 206+00.00 TO STA 212+00.00				
STA 212+00.00 TO STA 218+00.00				
STA 218+00.00 TO STA 224+00.00	1			
STA 224+00.00 TO STA 230+00.00	1			
STA 230+00.00 TO STA 236+00.00				
STA 236+00.00 TO STA 242+00.00	1			
STA 242+00.00 TO STA 248+00.00	4			
STA 248+00.00 TO STA 254+00.00	2			
STA 254+00.00 TO STA 260+00.00	1			
STA 260+00.00 TO STA 266+00.00				
STA 266+00.00 TO STA 272+00.00			194.70	
STA 272+00.00 TO STA 278+00.00	1			
STA 278+00.00 TO STA 284+00.00				
STA 201+45.35 TO STA 227+00.00				
STA 227+00.00 TO STA 270+78.11				
N. SCHOOL STREET				
STA 8+00.00 TO STA 14+00.00			696.70	
STA 14+00.00 TO STA 19+00.00			481.74	
STA 8+00.00 TO STA 14+00.00				
STA 14+00.00 TO STA 19+00.00				
STA 8+00.00 TO STA 14+00.00				577.41
STA 14+00.00 TO STA 19+00.00				258.19
STA 8+00.00 TO STA 14+00.00				119.29
STA 14+00.00 TO STA 19+00.00				223.62
STAGE II				
STA 194+00.00 TO STA 200+00.00				
STA 200+00.00 TO STA 206+00.00				
STA 206+00.00 TO STA 212+00.00				
STA 212+00.00 TO STA 218+00.00				
STA 218+00.00 TO STA 224+00.00	1			

MAINTENANCE OF TRAFFIC SCHEDULE	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 2	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	TEMPORARY PAVEMENT	TEMPORARY PAVEMENT REMOVAL
LOCATION	EACH	EACH	SQ YD	SQ YD
STAGE III				
STA 224+00.00 TO STA 230+00.00		1		
STA 230+00.00 TO STA 236+00.00				
STA 236+00.00 TO STA 242+00.00				
STA 242+00.00 TO STA 248+00.00				
STA 248+00.00 TO STA 254+00.00				
STA 254+00.00 TO STA 260+00.00		1	31.39	
STA 260+00.00 TO STA 266+00.00				
STA 266+00.00 TO STA 272+00.00				194.70
STA 272+00.00 TO STA 278+00.00				
STA 278+00.00 TO STA 284+00.00				
S. SCHOOL STREET				
STA 3+85.00 TO STA 10+00.00		2	1163.11	
STA 3+85.00 TO STA 10+00.00		2		268.88
STA 3+85.00 TO STA 10+00.00				894.22
POST STAGE III				
STA 201+45.35 TO STA 270+78.11				
STA 194+00.00 TO STA 200+00.00				
STA 200+00.00 TO STA 206+00.00				
STA 206+00.00 TO STA 212+00.00				
STA 212+00.00 TO STA 218+00.00				
STA 218+00.00 TO STA 224+00.00				
STA 224+00.00 TO STA 230+00.00				
STA 230+00.00 TO STA 236+00.00				
STA 236+00.00 TO STA 242+00.00				
STA 242+00.00 TO STA 248+00.00				
STA 248+00.00 TO STA 254+00.00				
STA 254+00.00 TO STA 260+00.00		1	31.39	
STA 260+00.00 TO STA 266+00.00				
STA 266+00.00 TO STA 272+00.00				
STA 272+00.00 TO STA 278+00.00				
STA 278+00.00 TO STA 284+00.00				

MAINTENANCE OF TRAFFIC SCHEDULE	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 2	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	TEMPORARY PAVEMENT	TEMPORARY PAVEMENT REMOVAL
LOCATION	EACH	EACH	SQ YD	SQ YD
STA 260+00.00 TO STA 266+00.00				
STA 266+00.00 TO STA 272+00.00				
STA 272+00.00 TO STA 278+00.00				
STA 278+00.00 TO STA 284+00.00				
SUB-TOTAL	13.00	12.00	4460.79	4460.84
TOTAL	13	12	4461	4461

FILE NAME	USER NAME	DESIGNED	REVISED
W:\p\j\j\20080356\DNV04-Rtbl\spc\5	1001	DRAWN	REVISED
		CHECKED	REVISED
		DATE	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**FAP 399 (IL RTE. 8)
SCHEDULE OF QUANTITIES**

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
399	36 R-7	TAZEWELL	390	37
CONTRACT NO. 68370			ILLINOIS FED. AID PROJECT	