



SCHEDULE OF QUANTITIES		
ITS FIBER (IL 8 FROM ILLINI DRIVE TO CAMPUS AVE.)		
PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	25.0
SIDEWALK REMOVAL	SQ FT	25.0
SERVICE INSTALLATION, TYPE B	EACH	1.0
UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	300.0
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	946.5
CONCRETE FOUNDATION, TYPE E 36 INCH DIAMETER	FOOT	14.5
DRILL EXISTING HANDHOLE	EACH	1.0
CAMERA POLE, 45 FT	EACH	1.0
POLE MOUNTED EQUIPMENT CABINET, TYPE B	EACH	1.0
CAT 5 ETHERNET CABLE	FOOT	40.0
CLOSED-CIRCUIT TELEVISION DOME CAMERA, IP BASED	EACH	1.0
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	9321.0

- UNDGRD C PVC 2 100.0 FT.
- EC C XLP USE 1C 6 946.5 FT.
- UNDGRD C PVC 2 200.0 FT.
- CCTV DOME CAMERA (IP BASED) 1.0 EACH
- CAMERA POLE, 45 FT 1.0 EACH
- CONC FDN TY E 36D 14.5 FT.
- POLE MT EQUIP CAB TB 1.0 EACH
- CAT 5 ETHERNET CABLE 40.0 FT.
- DRILL EX HH 1.0 EACH
- SIDEWALK REMOVAL 25.0 SO. FT.
- PC CONC SIDEWALK 4 25.0 SO. FT.

FILE NAME = P:\IL 8 ITS Fiber Plans\68370\IL 8 ITS	USER NAME = howlde	DESIGNED -	REVISED -
Plans\68370 - IL 8 ITS Fiber Plans (Final 10-10-10)	DRAWN -	REVISED -	REVISED -
PLOT SCALE = 75.0000' / 1" =	CHECKED -	REVISED -	REVISED -
PLOT DATE = 10/25/2011	DATE -	REVISED -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PROPOSED FIBER OPTIC CABLE INSTALLATION
IN EXISTING CONDUIT AND COMMUNICATION VAULTS**

SCALE: NONE ITS FIBER SHEET 2 OF 13 STA. _____ TO STA. _____

F.A.P. RTE. 399	SECTION 36R-7	COUNTY TAZEWELL	TOTAL SHEETS 390	SHEET NO. 263
CONTRACT NO. 68370			ILLINOIS FED. AID PROJECT	