


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				FAP 698 ROADWAY 0004 RURAL	80% FED 20% STATE BOX CULVERT 0011 SN 078-2009	BOX CULVERT 0011 SN 078-2010	100% STATE FAP 698 ROADWAY 0004 RURAL
50800515	BAR SPLICERS	EACH	190		104	86	
51500100	NAME PLATES	EACH	2		1	1	
54003000	CONCRETE BOX CULVERTS	CU YD	413.5		259.4	154.1	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	121	121			
54213459	END SECTIONS 24"	EACH	4	4			
63200310	GUARDRAIL REMOVAL	FOOT	837	837			
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	16	16			
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	5	5			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7			
67100100	MOBILIZATION	L SUM	1	1			
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1			
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			

X SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER	DESIGNED -	REVISED -
...Plans\0468571-shr-S00.DGN		DRAWN -	REVISED -
 Johnson, Depp & Quisenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 28.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/15/2011 10:37:32	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 4 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
698	(2) BR-1 & BR-2	PUTNAM	71	7
				CONTRACT NO. 68571
ILLINOIS FED. AID PROJECT				