


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				FAP 698 ROADWAY 0004 RURAL	80% FED 20% STATE	BOX CULVERT 0011 SN 078-2009	BOX CULVERT 0011 SN 078-2010	100% STATE	FAP 698 ROADWAY 0004 RURAL	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1						
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5						
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6						
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	0.5	0.5						
70300100	SHORT TERM PAVEMENT MARKING	FOOT	485	485						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3640	3640						
X 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2075	2075						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1269	1269						
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1525	1525						
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1100	1100						
X 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3640	3640						
X 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	21	21						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	548	548						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	21	21						

X SPECIALTY ITEMS

FILE NAME = ...\\Plans\0468571-ht-500.DGN	USER NAME = *USER*	DESIGNED -	REVISED -
 Johnson, Depp & Quisenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 28.0000 "/ IN.	DRAWN -	REVISED -
	PLOT DATE = 12/15/2011 10:39:52	CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 5 OF 6 SHEETS	STA.	TO STA.

F.A.P. RTE. 698	SECTION (2) BR-1 & BR-2	COUNTY PUTNAM	TOTAL SHEETS 71	SHEET NO. 8
CONTRACT NO. 68571			ILLINOIS FED. AID PROJECT	