

SUMMARY OF QUANTITIES				80% FEDERAL 20% STATE CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0004 ROADWAY	0011 STRUCTURE SN 055-0080	0011 STRUCTURE SN 055-0081
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	993	993		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1666	1666		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	11	11		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	125	125		
44000100	PAVEMENT REMOVAL	SQ YD	3849	3849		
44004250	PAVED SHOULDER REMOVAL	SQ YD	3079	3079		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	711	711		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	783	783		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		1	1
50105220	PIPE CULVERT REMOVAL	FOOT	203	203		
50200100	STRUCTURE EXCAVATION	CU YD	178		94	84
50300100	FLOOR DRAINS	EACH	22		10	12
50300225	CONCRETE STRUCTURES	CU YD	194.3		106.6	87.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	781.8		428.2	353.6
50300260	BRIDGE DECK GROOVING	SQ YD	1706		952	754
50300300	PROTECTIVE COAT	SQ YD	2052		1125	927
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0.5	0.5
50500505	STUD SHEAR CONNECTORS	EACH	5499		2961	2538
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	203190		111340	91850
50800515	BAR SPLICERS	EACH	204		112	92
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	2785		1309	1476
51202305	DRIVING PILES	FOOT	2785		1309	1476
51203200	TEST PILE METAL SHELLS	EACH	4		2	2
51500100	NAME PLATES	EACH	2		1	1
52100520	ANCHOR BOLTS, 1"	EACH	52		28	24
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	80	80		
542A1099	PIPE CULVERTS, CLASS A, TYPE 2 54"	FOOT	54	54		
542D0265	PIPE CULVERTS, CLASS D, TYPE 1 60"	FOOT	44	44		
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18"(TEMPORARY)	FOOT	520	520		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2		

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED - 12/12/11 (SRUCT #)
P:\07Files\070286\Phase2\CADD Sheets\048691-shs-summary.dgn		DRAWN -	REVISED -
	PLOT SCALE = 103.1218 "/ IN.	CHECKED -	REVISED -
	PLOT DATE = 12/13/2011	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: none SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(38B-2)BR	MCDONOUGH	130	4
CONTRACT NO. 68691				
ILLINOIS FED. AID PROJECT				