

SUMMARY OF QUANTITIES				80% FEDERAL 20% STATE CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0004 ROADWAY	0011 STRUCTURE SN 055-0080	0011 STRUCTURE SN 055-0081
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	2	2		
54215595	METAL END SECTIONS 60"	EACH	1	1		
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	254		138	116
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	20	20		
60107600	PIPE UNDERDRAINS 4"	FOOT	1296	1296		
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	132	132		
60222805	MANHOLES, TYPE A, 5'-DIAMETER, WITH MEDIAN INLET (604106)	EACH	1	1		
60500060	REMOVING INLETS	EACH	1	1		
X 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	975	975		
X 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1		
X 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6		
X 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6		
X 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	1		
63200310	GUARDRAIL REMOVAL	FOOT	1595	1595		
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	2	2		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	3	3		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18		
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	18	18		
67100100	MOBILIZATION	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	450	450		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	141	141		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10913	10913		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1420	1420		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	702	702		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	43	43		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	20709	20709		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	12096	12096		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2204.0	2204.0		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2204.0	2204.0		
70500100	TEMPORARY STEEL PLATE BEAM GUARDRAIL,TYPE A	FOOT	62.5	62.5		

X SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED - 12/12/11 (SRUCT *)
Pr\07Files\070206\Phase2\CADD Sheets\04	86691*shl*summary.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/13/2011	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: none SHEET NO. 3 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(38B-2)BR	MCDONOUGH	130	5
CONTRACT NO. 68691				
ILLINOIS FED. AID PROJECT				