

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0004	0004	0021	0004	0004
				TAZEWELL CO. URBAN	TAZEWELL CO. RURAL	TAZEWELL CO. RURAL	TAZEWELL CO. URBAN	TAZEWELL CO. RURAL
				90/10	90/10	90/10	100 STATE	100 STATE
				LOIEJ	LOIEA	LOIEA	07A03	07A0A
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	3,073	2,014	1,059			
40600990	TEMPORARY RAMP	SQ YD	1,636	280	1,356			
40603216	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-12.5, N90	TON	38,230	6,260	31,970			
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7,017	263	6,754			
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	26,006	4,663	21,343			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	494,021	54,131	439,890			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	9,280		9,280			
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	9,581	1,772	7,809			
44004250	PAVED SHOULDER REMOVAL	SQ YD	60,856	16,009	44,847			
44200561	CLASS A PATCHES, TYPE I, 11 INCH	SQ YD	20	20				
44200565	CLASS A PATCHES, TYPE II, 11 INCH	SQ YD	97	97				
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SQ YD	1,560	1,560				
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	43	43				
44201299	DOWEL BARS 1 1/2"	EACH	112	112				
44213000	PATCHING REINFORCEMENT	SQ YD	1,725	1,725				
44213200	SAW CUTS	FOOT	5,676	5,676				
44213204	TIE BARS 3/4"	EACH	950	950				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	20,978	3,745	17,233			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	59,978	10,641	49,337			
50800105	REINFORCEMENT BARS	POUND	17		17			
54002020	EXPANSION BOLTS 3/4 INCH	EACH	4		4			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1		1			

FILE NAME = D:\68914-1-155 Typicals.dgn
 USER NAME = johnsonsv
 PLOT SCALE = 100.0000' / 1" in.
 PLOT DATE = 1/13/2012

DESIGNED -	REVISOR -
DRAWN -	REVISIONS -
CHECKED -	REVISIONS -
DATE -	REVISIONS -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

NOT TO SCALE SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	901108RS-4(107,106,106XRS-2)	TAZEWELL	92	5
CONTRACT NO. 68914				
ILLINOIS FED. AID PROJECT				