

TABULATION OF RESURFACING QUANTITIES (CONTINUED)

LOCATION	PCC SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL, 1 1/2 IN	HMA SURFACE REMOVAL, 3 3/4 IN	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)			POLYMERIZED HMA SURFACE COURSE, MIX "E", N90	POLYMERIZED HMA SURFACE COURSE, MIX "D", N70	POLYMERIZED HMA BINDER COURSE, IL-12.5, N90	POLYMERIZED LEVELING BINDER (MM) IL-4.75, N50	HMA BASE CSE WIDENING 10 3/4 IN	HMA BASE CSE 10 3/4 IN
						COLD-MILLED	EXIST. PVMT.	FOG COAT						
						SQ YD	SQ YD	SQ YD						
I-155 NORTHBOUND LANES														
STA. 31+85.00 TO STA. 32+75.00		400.00	44.44			0.14			33.60					
STA. 32+75.00 TO STA. 44+93.42							0.71	0.71	272.93		409.39	136.46		
STA. 44+93.42 TO STA. 45+23.42	80.00		13.33			0.03			6.72					
STA. 45+23.42 TO STA. 48+97.25							OMISSION S.N. 090-0125							
STA. 48+97.25 TO STA. 49+27.25	80.00		13.33			0.03			6.72					
STA. 49+27.25 TO STA. 59+15.51						0.90	0.58	0.58	221.37		332.06	110.69		
STA. 59+15.51 TO STA. 60+75.51	400.00		26.67			0.15			35.84			17.92		
STA. 60+75.51 TO STA. 62+57.51							OMISSION S.N. 090-0129							
STA. 62+57.51 TO STA. 64+17.51	454.82		26.67			0.15			35.84			17.92		
STA. 64+17.51 TO STA. 73+45.00							0.54	0.54	207.76		311.64	103.88		
STA. 73+45.00 TO STA. 167+06.37 BK						24,963.65	8.49	5.49	2096.95		3175.66	5.04		
STA. 164+34.54 AH TO STA. 241+81.79						20,659.32	7.02	4.55	1735.38		2603.07			
STA. 241+81.79 TO STA. 246+38.96							1,219.12	0.41	102.41		153.61			
STA. 246+38.96 TO STA. 343+75.43						25,963.93	8.83	5.71	2180.97		3271.46			
STA. 343+75.43 TO STA. 344+05.43		80.00	13.33				0.03		6.72					
STA. 344+05.43 TO STA. 347+88.47							OMISSION S.N. 090-0135							
STA. 347+88.47 TO STA. 348+18.47		80.00	13.33				0.03		6.72					
STA. 348+18.47 TO STA. 606+47.59 BK						68,877.65	23.42	15.15	5785.72		8678.58			
STA. 608+08.87 AH TO STA. 611+43.78						893.08	0.30	0.20	75.02		112.53			
STA. 611+43.78 TO STA. 615+96.95							1,208.45	0.41	101.51		152.27			
STA. 615+96.95 TO STA. 616+26.95		133.33	22.22				0.05		11.20					
NORTHBOUND LANES SUB-TOTAL:	1,014.82	693.33	173.33	141,357.64	2,427.57	50.36	1.84	33.47	12,923.37		19,200.26			