

TABULATION OF SHOULDER QUANTITIES (CONTINUED)

LOCATION	WIDTH		HMA SURFACE REMOVAL, 1 1/2"	HMA SURFACE REMOVAL, 2"	HMA SURFACE REMOVAL, 3 3/4"	PAVED SHOULDER REMOVAL		SUBBASE GRAN. MAT., TYPE C	BIT. MAT. (PRIME COAT)	POLYMERIZED BIT. MAT. (PRIME COAT)		HMA SHOULDERS		SHOULDER RUMBLE STRIPS, 16 INCH		AGGREGATE SHOULDER REMOVAL	AGGREGATE SHOULDERS, TYPE B	
	LT	RT				LT	RT			GRAN. SUBBASE	COLD-MILLED	FOG COAT	LT	RT	LT			RT
	FT		SQ YD	SQ YD	SQ YD	SQ YD		TON	TON				TON		TON		FT	
I-155 NORTHBOUND LANES																		
STA. 32+75.00 TO STA. 44+26.04	0.00	6.00					767.36	466.55	1.53		0.17		343.78		1,151.04	56.81	203.85	
STA. 44+26.04 TO STA. 45+23.42	10.00	6.00				108.20	64.92	83.88	0.35		0.04	48.47	29.08	97.38	97.38	13.22	27.10	
STA. 45+23.42 TO STA. 46+11.42	10.00	6.00	97.78				58.67	35.67	0.12	0.03	0.03	20.53	26.28					
STA. 46+11.42 TO STA. 48+09.25	OMISSION S.N. 090-0125																	
STA. 48+09.25 TO STA. 48+97.25	10.00	6.00				97.78	58.67	75.80	0.31		0.03	43.80	26.28					
STA. 48+97.25 TO STA. 55+50.00	10.00	6.00				725.28	435.17	562.24	2.32		0.26	324.92	194.95	652.75	652.75	88.60	181.64	
STA. 55+50.00 TO STA. 57+15.39	10.00	6.00	183.77				110.26	67.04	0.22	0.06	0.06	51.45	49.40	165.39	165.39	8.16	34.87	
STA. 57+15.39 TO STA. 59+45.51	0.00	6.00					153.41	93.28	0.31		0.03		68.73		230.12	11.36	40.75	
STA. 59+45.51 TO STA. 60+00.00	0.00	6.00					36.33	22.09	0.07		0.01		16.27					
STA. 60+00.00 TO STA. 60+75.51	0.00	6.00	50.34										10.57					
STA. 60+33.51 TO STA. 62+58.95	OMISSION S.N. 090-0129																	
STA. 62+58.95 TO STA. 63+80.12	0.00	6.00					80.78	49.11	0.16		0.02		36.19					
STA. 63+80.12 TO STA. 73+45.00	10.00	6.00				1,072.09	643.25	831.08	3.43		0.38	480.30	288.18	1,444.88	1,444.88	130.97	268.50	
STA. 73+45.00 TO STA. 78+25.00	10.00	6.00				533.33	320.00	413.44	1.71		0.19	238.93	143.36	2,038.52	2,038.52	65.16	133.57	
STA. 78+25.00 TO STA. 93+83.52	10.00	6.00	2,770.70								0.94	363.65	218.19	1,558.52	1,558.52		144.56	
STA. 93+83.52 TO STA. 105+33.52	0.00	6.00	766.67								0.26	161.00	161.00		1,150.00		67.89	
STA. 105+33.52 TO STA. 127+00.00	10.00	6.00	3,851.52								1.31	505.51	303.31	2,166.48	2,166.48		200.95	
STA. 127+00.00 TO STA. 145+10.00	10.00	6.00	2,011.11			1,206.67	733.65	2.41	0.68	0.71	0.71	422.33	540.59	1,810.00	1,810.00	89.33	381.59	
STA. 145+10.00 TO STA. 150+97.22	10.00	6.00	1,043.95								0.35	137.02	82.21	587.22	587.22		54.47	
STA. 150+97.22 TO STA. 157+57.29	0.00	6.00	440.05								0.15	92.41	92.41		660.07		38.97	
STA. 157+57.29 TO STA. 167+06.37 BK	10.00	6.00	1,687.25								0.57	221.45	132.87	949.08	949.08		88.03	
STA. 164+34.54 AH TO STA. 171+33.74	10.00	6.00	1,243.02								0.42	163.15	97.89	699.20	699.20		64.86	
STA. 171+33.74 TO STA. 182+83.74	0.00	6.00	766.67								0.26	0.00	161.00		1,150.00		67.89	
STA. 182+83.74 TO STA. 203+55.32	10.00	6.00	3,682.81								1.25	483.37	290.02	2,071.58	2,071.58		192.15	
STA. 203+55.32 TO STA. 210+15.39	0.00	6.00	440.05								0.15	92.41	92.41		660.07		38.97	
STA. 210+15.39 TO STA. 237+50.00	10.00	6.00	4,861.53								1.65	638.08	382.85	2,734.61	2,734.61		253.65	
STA. 237+50.00 TO STA. 241+81.79	10.00	6.00	479.77				287.86	175.02	0.58	0.16	0.17	100.75	128.96	431.79	431.79	21.31	91.03	
STA. 241+81.79 TO STA. 246+38.96	10.00	6.00			507.97		304.78	185.31	0.61	0.17	0.18	106.67	136.54	457.17	457.17	22.56	96.38	
STA. 246+38.96 TO STA. 247+50.00	10.00	6.00	123.38				74.03	45.01	0.15	0.04	0.04	25.91	33.16	111.04	111.04	5.48	23.41	
STA. 247+50.00 TO STA. 279+60.00	10.00	6.00	5,706.67								1.94	749.00	449.40	3,210.00	3,210.00		297.75	
STA. 279+60.00 TO STA. 313+40.00	10.00	6.00	2,253.33			3,755.56		1,541.28	7.51	0.77	1.32	1,682.49	473.20	3,380.00	3,380.00	166.81	541.49	
STA. 313+40.00 TO STA. 324+89.82	10.00	6.00				1,277.58	766.55	990.38	4.09		0.45	572.35	343.41	1,149.82	1,149.82	156.08	319.96	
STA. 324+89.82 TO STA. 336+33.00	0.00	6.00					762.12	463.37	1.52		0.17		341.43		1,143.18	56.42	202.45	
STA. 336+33.00 TO STA. 344+05.43	10.00	6.00				858.26	514.95	665.32	2.75		0.30	384.50	230.70	772.43	772.43	104.85	214.94	
STA. 344+05.43 TO STA. 344+93.43	10.00	6.00				97.78	58.67	75.80	0.31		0.03	43.80	26.28					
STA. 344+93.43 TO STA. 347+00.47	OMISSION S.N. 090-0135																	
STA. 347+00.47 TO STA. 347+88.47	10.00	6.00	58.67			97.78		40.13	0.20	0.02	0.03	43.80	12.32					
STA. 347+88.47 TO STA. 353+50.00	10.00	6.00	374.35			623.92		256.06	1.25	0.13	0.22	279.52	78.61	561.53	561.53	27.71	89.96	
STA. 353+50.00 TO STA. 356+36.13	10.00	6.00	508.68								0.17	66.76	40.06	286.13	286.13		26.54	
STA. 356+36.13 TO STA. 362+93.26	0.00	6.00	438.09								0.15	92.00	92.00		657.13		38.79	
STA. 362+93.26 TO STA. 363+00.00	10.00	6.00	11.98									1.57	0.94	6.74	6.74	0.33	0.63	
STA. 363+00.00 TO STA. 377+50.00	10.00	6.00	966.67			1,611.11		661.20	3.22	0.33	0.57	721.78	203.00	1,450.00	1,450.00	71.56	232.30	
STA. 377+50.00 TO STA. 392+50.00	10.00	6.00				1,666.67	1,000.00	1,292.00	5.33		0.59	746.67	448.00	1,500.00	1,500.00	203.61	417.40	
STA. 392+50.00 TO STA. 402+50.00	10.00	6.00	666.67			1,111.11		456.00	2.22	0.23	0.39	497.78	140.00	1,000.00	1,000.00	49.35	160.20	
STA. 402+50.00 TO STA. 421+00.00	10.00	6.00	3,288.89								1.12	431.67	259.00	1,850.00	1,850.00		171.60	
STA. 421+00.00 TO STA. 431+00.00	10.00	6.00	1,111.11				666.67	405.33	1.33	0.38	0.39	233.33	298.67	1,000.00	1,000.00	49.35	210.82	
STA. 431+00.00 TO STA. 490+75.92	10.00	6.00	10,623.86								3.61	1,394.38	836.63	5,975.92	5,975.92		554.30	
STA. 490+75.92 TO STA. 502+25.92	0.00	6.00	766.67								0.26	161.00	161.00		1,150.00		67.89	
STA. 502+25.92 TO STA. 523+05.98	10.00	6.00	3,697.88								1.26	485.35	291.21	2,080.06	2,080.06		192.94	
STA. 523+05.98 TO STA. 529+65.98	0.00	6.00	440.00								0.15	92.40	92.40		660.00		38.96	

FILE NAME = D468914-1-155 Tpl0000.dgn

USER NAME = johnsonv
 PLOT SCALE = 1/8" = 100'-0" / 1"
 PLOT DATE = 1/13/2012

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET NO. 10 OF 27 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	9010BRS-4(107,106,106XRS-2)	TAZEVELL	92	33
CONTRACT NO. 68914				
[ILLINOIS] FED. AID PROJECT				