

PAVEMENT MARKING SCHEDULE (CONTINUED)

LOCATION	PREFORMED PLASTIC PVMT MARKING, TY B		URETHANE PAVEMENT MARKING,						RAISED REFLECTIVE PAVEMENT MARKER				
	LINE 6"		LINE 4"		LINE 8"		LINE 12"	LINE 24"	LINE 18"	ONE-WAY CRYSTAL 80' O.C.	ONE-WAY CRYSTAL 40' O.C.	ONE-WAY CRYSTAL 20' O.C.	ONE-WAY AMBER 40' O.C.
	SKIP DASH WHITE	FT	SOLID WHITE	SOLID YELLOW	SKIP DASH WHITE	SOLID WHITE	SOLID WHITE	SOLID WHITE	SOLID WHITE	EACH			
BIRCHWOOD INTERCHANGE													
RAMP A													
STA. 0+00	TO STA. 2+76		276								15		
STA. 2+76	TO STA. 6+60		384			384				11	19		
STA. 6+60	TO STA. 22+50		1,590	1,590								27	
STA. 22+50	TO STA. 23+05.92		56	56		154		20					
RAMP B													
STA. 0+31.55	TO STA. 3+00	30	268	268		578							
STA. 3+00	TO STA. 19+10	60	1,610	1,610									
STA. 19+10	TO STA. 26+42		732			732				19			
STA. 26+42	TO STA. 31+22.35		480										
RAMP C													
STA. 0+00	TO STA. 2+76		276								15		
STA. 2+76	TO STA. 6+28		352			352				10	18		
STA. 6+28	TO STA. 22+00		1,572	1,572								30	
STA. 22+00	TO STA. 23+27.22		127	127		588		20					
RAMP D													
STA. 0+34.62	TO STA. 18+83		1,848	1,848									
STA. 18+83	TO STA. 24+30		547			547				15			
STA. 24+30	TO STA. 31+37.71		708										
QUEENWOOD INTERCHANGE													
RAMP A													
STA. 0+00	TO STA. 2+16		216								12		
STA. 2+16	TO STA. 6+58		442			442				12	22		
STA. 6+58	TO STA. 16+00		942	942								11	
STA. 16+00	TO STA. 16+80.73		81	81		207	60						
RAMP B													
STA. 0+26.50	TO STA. 1+00		74	74		189	146						
STA. 1+00	TO STA. 8+88		788	788									
STA. 8+88	TO STA. 13+21		433			433				12			
STA. 13+21	TO STA. 20+64.60		744										
MAIN STREET INTERCHANGE													
RAMP C													
STA. 7+40.31	TO STA. 34+77		2,737	2,737									
STA. 34+77	TO STA. 39+41		464			464				13			
STA. 39+41	TO STA. 41+15.42		174										
RAMP D													
STA. 0+00	TO STA. 2+40		240								13		
STA. 2+40	TO STA. 6+60		420			420				12	21		
STA. 6+60	TO STA. 23+73.90		1,714	1,714								11	

FILE NAME = D468914-1-155 Typools.dgn

USER NAME = johnsonsv
 DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET NO. 16 OF 27 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	90108RS-4(107,106,106XIRS-2)	TAZEWELL	92	39
68914			CONTRACT NO. 68914	
ILLINOIS FED. AID PROJECT				