

PAVEMENT MARKING SCHEDULE (CONTINUED)

LOCATION	PREFORMED PLASTIC PVMT MARKING, TY B	URETHANE PAVEMENT MARKING,							RAISED REFLECTIVE PAVEMENT MARKER				
		LINE 6"	LINE 4"		LINE 8"		LINE 12"	LINE 24"	LINE 18"	ONE-WAY CRYSTAL 80' O.C.	ONE-WAY CRYSTAL 40' O.C.	ONE-WAY CRYSTAL 20' O.C.	ONE-WAY AMBER 40' O.C.
		SKIP DASH WHITE	SOLID WHITE	SOLID YELLOW	SKIP DASH WHITE	SOLID WHITE	SOLID WHITE	SOLID WHITE	SOLID WHITE				
		FT	FT		FT	FT	FT	FT	FT	EACH			
TOWNLINER INTERCHANGE													
RAMP A													
STA. 0+26.72	TO STA. 1+50		123	123		158	140						
STA. 1+50	TO STA. 8+47		697	697									
STA. 8+47	TO STA. 14+02		555			555				15			
STA. 14+02	TO STA. 20+85.64		684										
RAMP B													
STA. 0+00	TO STA. 2+64		264								14		
STA. 2+64	TO STA. 6+69		405			405				11	20		
STA. 6+69	TO STA. 18+50		1,181	1,181								7	
STA. 18+50	TO STA. 19+30.89		81	81		158	68	40					
RAMP C													
STA. 0+26.86	TO STA. 1+50		123	123		184	142						
STA. 1+50	TO STA. 8+29		679	679									
STA. 8+29	TO STA. 14+89		660			660				18			
STA. 14+89	TO STA. 20+89.49		600										
RAMP D													
STA. 0+00	TO STA. 2+28		228								12		
STA. 2+28	TO STA. 5+66		338			338				9	17		
STA. 5+66	TO STA. 17+00		1,134	1,134								8	
STA. 17+00	TO STA. 17+74.60		75	75		145	96	40					
SUBTOTAL:		58,647	142,560	142,560	2,562	21,851	2,410	280	72	1,673	492	327	131
TOTAL:		29,369	285,120	285,120	24,413	2,410	280	72	2,622				

NOTE: BUREAU OF OPERATIONS MUST BE CONTACTED TWO WEEKS PRIOR TO PLACING AERIAL SPEED ZONE PAVEMENT MARKINGS.