

EROSION CONTROL SCHEDULE

LOCATION	GRADING AND SHAPING DITCHES	TEMPORARY DITCH CHECKS	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 2A	EROSION CONTROL BLANKET	MULCH, METHOD 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	
	FT	FT	POUND 100 LB/ACRE	ACRE	SQ YD	ACRE	POUND 90 LB/ACRE	POUND 90 LB/ACRE	POUND 90 LB/ACRE	
I-155 MAINLINE										
STA. 113+36 TO STA. 114+06	CENTER MEDIAN S.N. 090-0130	70	16	9.64	0.05	62.22	0.05	4.34	4.34	4.34
STA. 136+00 TO STA. 138+00	SB DITCH	200	30	27.55	0.14	222.22	0.14	12.40	12.40	12.40
STA. 139+00 TO STA. 142+60	CENTER MEDIAN	360	24	49.59	0.25	320.00	0.25	22.31	22.31	22.31
STA. 154+60 TO STA. 156+00	CENTER MEDIAN	140	16	19.28	0.10	124.44	0.10	8.68	8.68	8.68
STA. 156+28 TO STA. 157+28	SB DITCH	100	20	13.77	0.07	111.11	0.07	6.20	6.20	6.20
STA. 160+00 TO STA. 175+00	NB DITCH	1,500	110	206.61	1.03	1,666.67	1.03	92.98	92.98	92.98
STA. 190+50 TO STA. 192+20	CENTER MEDIAN S.N. 090-0132	170	24	23.42	0.12	151.11	0.12	10.54	10.54	10.54
STA. 243+90 TO STA. 244+40	CENTER MEDIAN S.N. 090-0133	50	16	6.89	0.03	44.44	0.03	3.10	3.10	3.10
STA. 251+70 TO STA. 253+20	SB DITCH	150	20	20.66	0.10	166.67	0.10	9.30	9.30	9.30
STA. 295+00 TO STA. 296+00	CENTER MEDIAN	100	16	13.77	0.07	88.89	0.07	6.20	6.20	6.20
STA. 328+00 TO STA. 329+00	CENTER MEDIAN	100	16	13.77	0.07	88.89	0.07	6.20	6.20	6.20
STA. 350+93 TO STA. 352+83	CENTER MEDIAN	190	24	26.17	0.13	168.89	0.13	11.78	11.78	11.78
STA. 433+00 TO STA. 434+00	SB DITCH	100	20	13.77	0.07	111.11	0.07	6.20	6.20	6.20
STA. 467+95 TO STA. 468+95	SB DITCH	100	20	13.77	0.07	111.11	0.07	6.20	6.20	6.20
STA. 505+75 TO STA. 506+75	SB & NB DITCH, CENTER MEDIAN	300	56	41.32	0.21	311.11	0.21	18.60	18.60	18.60
STA. 510+40 TO STA. 511+10	CENTER MEDIAN S.N. 090-0136	70	16	9.64	0.05	62.22	0.05	4.34	4.34	4.34
BIRCHWOOD INTERCHANGE RAMPS C AND D										
STA. 17+10 TO STA. 20+00	RAMP C RT. DITCH	290	30	39.94	0.20	322.22	0.20	17.98	17.98	17.98
BROADWAY INTERCHANGE RAMP A										
STA. 6+00 TO STA. 12+00	RAMP A RT. DITCH	600	50	82.64	0.41	666.67	0.41	37.19	37.19	37.19
BROADWAY INTERCHANGE RAMP D										
STA. 10+00 TO STA. 10+50			10	4.94	0.02	55.56	0.02	2.22	2.22	2.22
STA. 10+50 TO STA. 11+00			10	10.26	0.05	55.56	0.05	4.62	4.62	4.62
STA. 11+00 TO STA. 11+50			10	10.74	0.05	55.56	0.05	4.83	4.83	4.83
STA. 11+50 TO STA. 12+00			10	11.03	0.06	55.56	0.06	4.96	4.96	4.96
STA. 12+00 TO STA. 12+50			10	11.45	0.06	55.56	0.06	5.15	5.15	5.15
STA. 12+50 TO STA. 13+00			10	11.93	0.06	55.56	0.06	5.37	5.37	5.37
STA. 13+00 TO STA. 13+50			10	13.23	0.07	55.56	0.07	5.95	5.95	5.95
STA. 13+50 TO STA. 14+00			10	7.15	0.04	55.56	0.04	3.22	3.22	3.22
SUB-TOTAL		4,590	574	712.95	3.56	5,244.44	3.5648	320.83	320.83	320.83
TOTAL		4,590	574	713	3.75	5,245	3.75	321	321	321

FILE NAME = 0468914-1-155 Typical.dgn

USER NAME = johnsonsv

DESIGNED -

REVISED -

PLOT SCALE = 100.0000' / 1"

CHECKED -

REVISED -

PLOT DATE = 1/9/2012

DATE -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET NO. 22 OF 27 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	90108RS-4(107.106.106XRS-2)	TAZEWELL	92	45
68914			CONTRACT NO. 68914	
ILLINOIS FED. AID PROJECT				