

**PIPE UNDERDRAIN SCHEDULE**

LOCATION	OUTLET	STATION	PIPE UNDERDRAINS 4"		PIPE UNDERDRAINS 4" (SPECIAL)		REMOVE AND REPLACE CONCRETE HEADWALL FOR PIPE DRAINS		PIPE UNDERDRAIN REMOVAL	
			OUTSIDE SHOULDER	MEDIAN	OUTSIDE SHOULDER	MEDIAN	OUTSIDE SHOULDER	MEDIAN		
			FOOT		FOOT		EACH			FOOT
<b>I-155 SOUTHBOUND LANES</b>										
STA. 33+00.00	STA. 37+50.00	SHOULDER	37+50.00	450.00	450.00	18.00	15.00	1	1	900.00
STA. 37+50.00	STA. 42+00.00	SHOULDER	42+00.00	450.00	450.00	18.00	15.00	1	1	900.00
STA. 42+00.00	STA. 46+11.42			411.42	411.42					822.84
STA. 48+19.00	STA. 50+50.00	SHOULDER	48+19.00	231.00	231.00	18.00	15.00	1	1	462.00
STA. 50+50.00	STA. 55+50.00	SHOULDER	55+50.00	500.00	500.00	18.00	15.00	1	1	1000.00
STA. 55+50.00	STA. 59+75.51	SHOULDER	59+75.51		425.51		15.00		1	425.51
STA. 62+70.95	STA. 65+00.00				229.05					229.05
STA. 65+00.00	STA. 68+00.00	SHOULDER	68+00.00	300.00	300.00	18.00	15.00	1	1	600.00
STA. 68+00.00	STA. 73+00.00	CULVERT	73+00.00	500.00	500.00					1000.00
STA. 73+00.00	STA. 76+50.00	SHOULDER	76+50.00	350.00	350.00	18.00		1		700.00
STA. 76+50.00	STA. 78+25.00	SHOULDER	78+25.00		175.00		15.00		1	175.00
STA. 78+25.00	STA. 83+25.00	SHOULDER	83+25.00		500.00		15.00		1	500.00
STA. 83+25.00	STA. 88+25.00	CULVERT	88+25.00		500.00					500.00
STA. 88+25.00	STA. 91+00.00				275.00					275.00
STA. 91+00.00	STA. 94+70.00	SHOULDER	94+70.00		370.00	19.00	24.00	1	1	370.00
STA. 94+70.00	STA. 100+78.00	SHOULDER	94+70.00	608.00		19.00		1		608.00
STA. 100+78.00	STA. 103+00.00	CULVERT	103+00.00	222.00						222.00
STA. 112+50.00	STA. 122+50.00	SHOULDER	112+50.00	1000.00		19.00		1	1	1000.00
		SHOULDER	122+50.00				17.00			
STA. 122+50.00	STA. 127+00.00	SHOULDER	127+00.00		450.00		17.00		1	450.00
STA. 127+00.00	STA. 131+50.00	SHOULDER	131+50.00		450.00		17.00		1	450.00
STA. 131+50.00	STA. 136+00.00	SHOULDER	136+00.00		450.00		17.00		1	450.00
STA. 136+00.00	STA. 140+50.00	SHOULDER	140+50.00		450.00		17.00		1	450.00
STA. 140+50.00	STA. 145+10.00	CULVERT	145+10.00		460.00					460.00
STA. 160+00.00	STA. 163+50.00	SHOULDER	163+50.00		350.00		17.00		1	350.00
STA. 163+50.00	STA. 167+06.37 BK				356.37					356.37
STA. 164+34.54 AH	STA. 165+50.00	SHOULDER	165+50.00		115.46		17.00		1	115.46
STA. 165+50.00	STA. 170+15.00	CULVERT	170+15.00		465.00					465.00
		SHOULDER	185+00.00				17.00			
STA. 185+00.00	STA. 190+00.00	SHOULDER	190+00.00		500.00		17.00		1	500.00
STA. 190+00.00	STA. 195+35.00	SHOULDER	195+35.00		535.00		17.00		1	535.00
STA. 195+35.00	STA. 200+69.00	CULVERT	200+69.00		534.00					534.00
STA. 200+69.00	STA. 205+70.00	SHOULDER	205+70.00		501.00		17.00		1	501.00
		SHOULDER	218+00.00			19.00	17.00	1	1	
STA. 218+00.00	STA. 223+00.00	CULVERT	223+00.00	500.00	500.00					1000.00
STA. 223+00.00	STA. 228+00.00	SHOULDER	228+00.00		500.00		17.00		1	500.00
		SHOULDER	237+50.00				17.00		1	
STA. 237+50.00	STA. 242+50.00	SHOULDER	242+50.00		500.00	19.00	17.00	1	1	500.00
STA. 242+50.00	STA. 247+50.00	SHOULDER	247+50.00	500.00	500.00	19.00	17.00	1	1	1000.00
STA. 247+50.00	STA. 252+50.00	SHOULDER	252+50.00		500.00	19.00	17.00	1	1	500.00
STA. 252+50.00	STA. 257+50.00	SHOULDER	257+50.00	500.00	500.00	19.00	17.00	1	1	1000.00
STA. 257+50.00	STA. 262+44.00	CULVERT	262+44.00		494.00					494.00
STA. 262+44.00	STA. 266+50.00	SHOULDER	266+50.00		406.00		17.00		1	406.00

FILE NAME = D:\68914-1-155\_Typicals.dgn  
 USER NAME = johnsonv  
 PLOT SCALE = 100.0000' / in.  
 PLOT DATE = 1/13/2012

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULES OF QUANTITIES**

NOT TO SCALE    SHEET NO. 23 OF 27 SHEETS    STA.    TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	9010BRS-4(107,106,106XRS-2)	TAZEWELL	92	46
68914		CONTRACT NO. 68914		
ILLINOIS FED. AID PROJECT				