

PIPE UNDERDRAIN SCHEDULE (CONTINUED)

LOCATION	OUTLET	STATION	PIPE UNDERDRAINS 4"		PIPE UNDERDRAINS 4" (SPECIAL)		REMOVE AND REPLACE CONCRETE HEADWALL FOR PIPE DRAINS		PIPE UNDERDRAIN REMOVAL
			OUTSIDE SHOULDER	MEDIAN	OUTSIDE SHOULDER	MEDIAN	OUTSIDE SHOULDER	MEDIAN	
			FOOT		FOOT		EACH		
I-155 NORTHBOUND LANES									
STA. 33+40.00	STA. 37+50.00	CULVERT		410.00					410.00
STA. 37+50.00	STA. 42+00.00	SHOULDER		450.00		15.00		1	450.00
STA. 42+00.00	STA. 46+11.42	SHOULDER		411.42		15.00		1	411.42
STA. 48+09.25	STA. 50+50.00	SHOULDER	240.75	240.75	18.00	15.00	1	1	481.50
STA. 50+50.00	STA. 55+50.00	SHOULDER	500.00	500.00	18.00	15.00	1	1	1000.00
STA. 55+50.00	STA. 60+00.00	CULVERT		450.00					450.00
STA. 62+92.12	STA. 68+00.00	SHOULDER	507.88	507.88	18.00	15.00	1	1	1015.76
STA. 68+00.00	STA. 73+00.00	CULVERT	500.00	500.00					1000.00
STA. 73+00.00	STA. 78+25.00	SHOULDER	525.00	525.00	18.00	15.00	1	1	1050.00
		SHOULDER				17.00		1	
STA. 127+00.00	STA. 131+50.00	SHOULDER		450.00		17.00		1	450.00
STA. 131+50.00	STA. 136+00.00	SHOULDER		450.00		17.00		1	450.00
STA. 136+00.00	STA. 140+50.00	SHOULDER		450.00		17.00		1	450.00
STA. 140+50.00	STA. 145+10.00	CULVERT		460.00					460.00
		SHOULDER				17.00		1	
STA. 237+50.00	STA. 242+50.00	SHOULDER		500.00		17.00		1	500.00
STA. 242+50.00	STA. 247+50.00	SHOULDER		500.00		17.00		1	500.00
		SHOULDER			19.00			1	
STA. 279+60.00	STA. 284+60.00	CULVERT	500.00						500.00
STA. 284+60.00	STA. 288+80.00	SHOULDER	420.00		19.00			1	420.00
STA. 288+80.00	STA. 293+50.00	SHOULDER	470.00		19.00			1	470.00
STA. 293+50.00	STA. 297+25.00	SHOULDER	375.00		19.00			1	375.00
STA. 297+25.00	STA. 303+40.00	CULVERT	615.00						615.00
STA. 303+40.00	STA. 308+40.00	SHOULDER	500.00		19.00			1	500.00
STA. 308+40.00	STA. 313+40.00	SHOULDER	500.00		19.00	17.00		1	500.00
STA. 313+40.00	STA. 316+25.00	CULVERT	285.00	285.00					570.00
STA. 316+25.00	STA. 321+25.00	SHOULDER	500.00	500.00	19.00	17.00		1	1000.00
STA. 321+25.00	STA. 326+25.00	SHOULDER	500.00	500.00		17.00		1	500.00
STA. 326+25.00	STA. 331+25.00	SHOULDER	500.00	500.00		17.00		1	500.00
STA. 331+25.00	STA. 333+50.00	SHOULDER		225.00		17.00		1	225.00
STA. 333+50.00	STA. 336+33.00	SHOULDER		283.00		17.00		1	283.00
STA. 336+33.00	STA. 340+08.00	SHOULDER	375.00	375.00	19.00	17.00		1	750.00
STA. 340+08.00	STA. 344+93.43		485.43	485.43					970.86
STA. 347+00.47	STA. 349+00.00	SHOULDER	199.53		19.00			1	199.53
STA. 349+00.00	STA. 353+50.00	SHOULDER	450.00		19.00			1	450.00
		SHOULDER			19.00			1	
STA. 363+00.00	STA. 367+50.00	SHOULDER	450.00		19.00			1	450.00
STA. 367+50.00	STA. 372+50.00	SHOULDER	500.00		19.00			1	500.00
STA. 372+50.00	STA. 377+50.00	SHOULDER	500.00		19.00	18.00		1	500.00
STA. 377+50.00	STA. 382+50.00	SHOULDER	500.00	500.00	19.00	18.00		1	1000.00
STA. 382+50.00	STA. 387+50.00	CULVERT	500.00	500.00					1000.00
STA. 387+50.00	STA. 392+50.00	SHOULDER	500.00	500.00	19.00	18.00		1	1000.00

FILE NAME = 0468914-1-155 Typicals.dgn
 USER NAME = johnstev
 PLDT SCALE = 100,0000' / 1" = 1000'
 PLOT DATE = 1/13/2012

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET NO. 25 OF 27 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	9010BR5-4(107,106,106XRS-2)	TAZEWELL	92	48
68914		CONTRACT NO. 68914		
ILLINOIS FED. AID PROJECT				