

PIPE UNDERDRAIN SCHEDULE (CONTINUED)											
LOCATION	OUTLET	STATION	PIPE UNDERDRAINS 4"		PIPE UNDERDRAINS 4" (SPECIAL)		REMOVE AND REPLACE CONCRETE HEADWALL FOR PIPE DRAINS		PIPE UNDERDRAIN REMOVAL		
			OUTSIDE SHOULDER	MEDIAN	OUTSIDE SHOULDER	MEDIAN	OUTSIDE SHOULDER	MEDIAN			
			FOOT		FOOT		EACH			FOOT	
<b>I-155 NORTHBOUND LANES</b>											
STA. 392+50.00	STA. 397+50.00	SHOULDER	397+50.00	500.00		19.00		1		500.00	
STA. 397+50.00	STA. 402+50.00	SHOULDER	402+50.00	500.00		19.00		1		500.00	
STA. 421+00.00	STA. 426+00.00	SHOULDER	421+00.00		500.00		18.00		1	500.00	
STA. 426+00.00	STA. 431+00.00	SHOULDER	430+50.00		500.00		18.00		1	500.00	
STA. 564+50.00	STA. 574+00.00	SHOULDER	564+50.00		950.00		18.00		1	950.00	
		SHOULDER	574+00.00				18.00		1		
<b>RAMP D</b>											
STA. 10+21.71	STA. 10+50.00	SHOULDER	10+21.71	28.29		17.00		1		28.29	
STA. 10+50.00	STA. 13+15.00	SHOULDER	10+21.71	265.00						265.00	
STA. 13+15.00	STA. 14+42.00			127.00						127.00	
<b>SUB TOTAL</b>					28,782.30	42,674.25	1,090.00	1,385.00	58	80	71456.55
<b>TOTAL</b>					71,457		2,475		138		71,457

CULVERT CLEANING SCHEDULE					
LOCATION	PIPE CULVERT TO BE CLEANED, 24"	PIPE CULVERT TO BE CLEANED, 36"	PIPE CULVERT TO BE CLEANED, 42"	CLEANING EXISTING INLETS	BOX CULVERTS TO BE CLEANED
	FOOT	FOOT	FOOT	EACH	EACH
<b>I-155 MAINLINE</b>					
STA. 54+75 (CMP)	50				1
STA. 62+70 S.N. 090-0129 (NB)				2	
STA. 88+25 (CMP)	63				
STA. 157+52 (CMP)	25				
STA. 223+00 24" PRECAST PIPE	82				
STA. 243+30 24" PRECAST PIPE	77				
STA. 256+00 24" PRECAST PIPE	45				
STA. 284+60 36" PRECAST PIPE		45			
STA. 538+80 36" PRECAST PIPE		136			
STA. 548+00 24" PRECAST PIPE	24				
STA. 556+33 4' X 2' BOX					1
STA. 570+52 24" PRECAST PIPE	164				
STA. 604+90 42" PRECAST PIPE			54		
STA. 613+36 24" PRECAST PIPE	54				
<b>TOTAL</b>	<b>584</b>	<b>181</b>	<b>54</b>	<b>2</b>	<b>1</b>

ISLAND PAVEMENT REMOVAL	
LOCATION	SQ YD
BROADWAY RAMP D	
STA. 14+00	29.42
<b>TOTAL</b>	<b>30</b>

CONCRETE MEDIAN, TYPE SM-6.24	
LOCATION	SQ FT
BROADWAY RAMP D	
STA. 14+00	392.92
<b>TOTAL</b>	<b>393</b>

FILE NAME = 0468914-1-155 Typicals.dgn

USER NAME = johnsonv  
 PLOT SCALE = 100,0000' / in.  
 PLOT DATE = 1/13/2012

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET NO. 26 OF 27 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	901108RS-4(107,106,106XRS-2)	TAZEWELL	92	49
68914		CONTRACT NO. 68914		
ILLINOIS FED. AID PROJECT				