

PATCHING SCHEDULE

LOCATION	CLASS A PATCHES - 11 IN					PATCHING REINFORCEMENT	SAW CUTS	TIE BARS 3/4"	CLASS A PATCHES, 11 IN (SPECIAL)	CLASS B PATCHES, 11 INCHES	DOWEL BARS 1 1/2"			
	SIZE	NO.	TYPE I	TYPE II	TYPE IV				TYPE II	TYPE II	EACH	SQ YD	SQ YD	EACH
			SQ YD	SQ YD	SQ YD				SQ YD	SQ YD				
NB STA. 65+00 TO STA. 71+60	660 X 6	1			440.00	440.00	1,344	330						
NB LANES	6 X 12	2		16.00		16.00	120							
NB LANES	120 X 12	2			320.00	320.00	576	120						
NB LANES	10 X 12	2		26.67		26.67	136							
NB STA. 37+00	50 X 12	3			200.00	200.00	444	75						
NB LANES STA. 51+50 TO STA. 55+50	400 X 6	1			266.67	266.67	824	200						
NB STA. 41+00 TO STA. 44+00	300 X 6	1			200.00	200.00	624	150						
NB DRIVING LANE	50 X 12	1			66.67	66.67	148	25						
NB DRIVING LANE	12 X 6	2		16.00		16.00	96							
NB DRIVING LANE	50 X 6	1			33.33	33.33	124	25						
NB PASSING LANE	6 X 6	1	4.00			4.00	36							
NB PASSING LANE	50 X 6	1			33.33	33.33	124	25						
NB PASSING LANE	12 X 6	1		8.00		8.00	48							
SB DRIVING LANES	6 X 6	4	16.00			16.00	144							
SB DRIVING LANES	10 X 6	1		6.67		6.67	44							
SB LANES	6 X 12	1		8.00		8.00	60							
SB LANES	6 X 12	2		16.00		16.00	120							
BIRCHWOOD INTERHCHANGE RAMP A	6 X 16	4					304			42.67	112			
NB LANES STA. 73+15	6 X 12	2				16.00	120		16.00					
SB LANES STA. 32+70	6 X 12	2				16.00	120		16.00					
SB LANES STA. 73+15	6 X 12	2				16.00	120		16.00					
TOTAL:			20	97	1,560	1,725	5,676	950	48	43	112			

CULVERT SCHEDULE

LOCATION	METAL END SECTIONS, 24"	INLET AND PIPE PROTECTION	REMOVE EXISTING FLARED END SECTION	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	CONCRETE COLLAR	EXPANSION BOLTS 3/4 INCH	REINFORCEMENT BARS
	EACH	EACH	EACH	EACH	CU YD	EACH	POUND
I-155 MAINLINE							
STA. 120+00	1	1					
STA. 157+52	1	1					
STA. 305+00		1	1	1	0.30	4	17
TOTAL	2	3	1	1	0.30	4	17

FILE NAME = 0460914-1-155 Typicals.dgn

USER NAME = johnsonv

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 100.0000' / in.

CHECKED -

REVISED -

PLOT DATE = 1/13/2012

DATE -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET NO. 27 OF 27 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	901108RS-4(107,106,106XRS-2)	TAZEWELL	92	50
68914			CONTRACT NO. 68914	
ILLINOIS FED. AID PROJECT				