



GENERAL NOTES

1. The work shall be done in accordance with Article 406.08 and the Special Provision for Butt Joints.
2. The pavement surface to be removed may be either bituminous or P.C. concrete. The work shall be performed in accordance with Article 440.04 and the Special Provisions for Butt Joints.
3. The saw cut joints shall be primed just prior to the placing of bituminous material. The work will be in accordance with the applicable portions of Article 406.05.

 REMOVAL LIMITS

FILE NAME =
D468914-1-155 Typical.dgn

USER NAME = johnsonsv
DESIGNED -
DRAWN -
CHECKED -
PLOT DATE = 1/9/2012

REVISIONS
REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PCC BUTT JOINT DETAIL
NOT TO SCALE SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	90108RS-4(107,106,106XRS-2)	TAZEWELL	92	72
CONTRACT NO. 68914				
ILLINOIS FED. AID PROJECT				