

L24E(F)

L53E(HSIP)

07CO

CONSTRUCTION CODE

FAP 0004	FAP 0004	FAP 0021	FAP 0021
80% FED	90% FEDERAL	90% FEDERAL	80% STATE
20% STATE	10% STATE	10% STATE	20% CITY
			SIDEWALK

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FAP 0004	FAP 0004	FAP 0021	FAP 0021
20200100	EARTH EXCAVATION	CU YD	91	91			
20400800	FURNISHED EXCAVATION	CU YD	1004	1004			
20800150	TRENCH BACKFILL	CU YD	53	53			
21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	3584	3584			
21400100	GRADING AND SHAPING DITCHES	FOOT	42		42		
X 25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75			
X 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	74	74			
X 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	74	74			
X 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	74	74			
X 25100115	MULCH, METHOD 2	ACRE	0.75	0.75			
X 25100630	EROSION CONTROL BLANKET	SQ YD	794	794			
X 25200110	SODDING, SALT TOLERANT	SQ YD	560	560			
X 25200200	SUPPLEMENTAL WATERING	UNIT	5.6	5.6			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	363	363			

X SPECIALTY ITEM

FILE NAME = 0412345-sht-500.dgn

USER NAME = rudzinski.jl
 PLOT SCALE = 100.0000' / 1" =
 PLOT DATE = 12/21/2011

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE. 399	SECTION 135.36IN-1	COUNTY TAZEWELL	TOTAL SHEETS 60	SHEET 6
CONTRACT NO. 68A66			ILLINOIS FED. AID PROJECT	