

L24E(F)

L53E (HSIP)

0700

CONSTRUCTION CODE

FAP 0004	FAP 0004	FAP 0021	FAP 0021
	SAFETY	SAFETY	80% STATE
80% FED	90% FEDERAL	90% FEDERAL	20% CITY
20% STATE	10% STATE	10% STATE	SIDEWALK

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FAP 0004	FAP 0004	FAP 0021	FAP 0021
X 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1273			1273	
X 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1063.5			1063.5	
X 87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	1442			1442	
X 87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	2			2	
X 87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1			1	
X 87703030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	1			1	
X 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3			3	
X 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10			10	
X 87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21			21	
X 87900200	DRILL EXISTING HANDHOLE	EACH	4			4	
X 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6			6	
X 88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	3			3	
X 88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST-ARM MOUNTED	EACH	1			1	
X 88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	2			2	

X SPECIALTY ITEM

FILE NAME = D412345-ah-500.dgn	USER NAME = rudinskijl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET
399	(35,36)N-1	TAZEWELL	60	10
			CONTRACT NO. 68A66	
ILLINOIS FED. AID PROJECT				