

EARTHWORK SUMMARY	EARTH EXCAVATION	FOR INFORMATION ONLY		FURNISHED EXCAVATION
		EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
IL 8 Mainline Station 270+50 to 283+97 LT	90.9	68.2	1072.6	1004.4
Earthwork Total	91			1004

REMOVALS			
LOCATION	PAVEMENT REMOVAL	MEDIAN REMOVAL	PAVED SHOULDER REMOVAL
	SQ. YD.	SQ. FT.	SQ. YD.
IL 8			
STA. 271+00 TO STA. 282+45.56 LT			1280
STA. 283+98.22 TO STA. 284+45.36 LT (MEDIAN)	23	251	
BUS. US 24 (McCLUGGAGE RD.)			
STA. 494+18.46 TO STA. 494+72.12	219	878	210
TOTALS	242	1129	1490

LOCATION	EROSION CONTROL BLANKET	TEMPORARY DITCH CHECKS	INLET AND PIPE PROTECTION	PERIMETER EROSION BARRIER
	SQ. FT.	FT.	EACH	FT.
IL 8				
STA. 271+00 TO 283+97 LT	794	144	11	350
BUS. US 24 (McCLUGGAGE RD.)				
STA. 494+02 TO 494+14				35
TOTALS	794	144	11	385

LOCATION	DETECTABLE WARNINGS
	SQ. FT.
BUS. US 24 (McCLUGGAGE RD.)	
STA. 494+31.43 TO STA. 494+72.12	93
TOTALS	93

LOCATION	GRADING AND SHAPING DITCHES
	FOOT
BUS US 24 STA 494+00 TO STA 494+42 (MEDIAN)	42
TOTAL	42

STORM SEWER REMOVALS				
LOCATION		REMOVING INLETS	STORM SEWER REMOVAL	REMOVE CONCRETE END SECTION
		EACH	FT.	EACH
STA 278+00.5	LT	1	24	1
STA 281+50	LT	1	40	1
TOTALS		2	64	2

LOCATION	FURNISH & PLACE TOPSOIL, 4"	SEEDING, CLASS A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2	SODDING, SALT TOLERANT	SUPPLEMENTAL WATERING	TEMPORARY EROSION CONTROL SEEDING
	SQ YD	ACRE	POUND	POUND	POUND	ACRE	SQ YD	UNIT	POUND
IL 8									
STA 271+00 to STA 283+97 LT	3,584.00	0.75	74	74	74	0.75	560.1	5.6	363
TOTALS	3,584	0.75	74	74	74	0.75	560	5.6	363

FILE NAME = D412345-ght-schedule.dgn

USER NAME = boyermj
 PLOT SCALE = 48,0000' / 1" =
 PLOT DATE = 12/19/2011

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
399	(35,36)N-1	TAZEWELL	60	14
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68A66	