INLETS									STORM SEWER			END SECTIONS				RIPRAP	
STRUCTURE NUMBER	STATION	OFFSET		GRATE TYPE	GRATE ELEVATION	FLOW LINE ELEVATION	INLET TYPE G-1 SPL	INLETS, TYPE G-1	STORM SEWER, CL A, TYPE 1 12"	SLOPE	TRENCH BACKFILL	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	OFFSET		FLOW LINE ELEVATION	STONE RIPRAP, CLASS B3	FILTER FABRIC
		FT					EACH	EACH	FOOT	%	CU YD	EACH	FT		ELEVATION	TON	SQ YD
IL 8																	
1	STA. 271+06.52	35.22	LT	VANE	800.81	797.81	1		30	6.69	5.46	1	74.65	LT	795.40	1.3	4
2	STA. 272+27	35.22	LT	VANE	800.48	797.98	1		18	1.25	3.78	1	63.07	LT	797.68	1.3	4
3	STA. 273+50	35.22	LT	VANE	799.82	797.32	1		18	1.05	3.78	1	62.89	LT	797.00	1.3	4
4	STA. 274+73	35.22	LT	VANE	799.47	796.97	1		19	2.00	3.78	1	63.8	LT	796.47	1.3	4
5	STA. 276+31	35.22	LT	VANE	798.76	796.26	1		20	1.50	3.10	1	64.94	LT	795.87	1.3	4
6	STA. 278+00	35.22	LT	VANE	797.62	795.04	1		20	1.65	3.78	1	65.09	LT	794.61	1.3	4
7	STA. 280+23	35.22	LT	VANE	795.36	792.40	1		32	6.80	4.45	1	76.47	LT	789.82	1.3	4
8	STA. 281+50	35.22	LT	VANE	793.89	788.91	1		38	3.94	11.14	1	82.6	LT	787.18	1.3	4
9	STA. 283+36	45.92	LT	VANE	791.22	787.22		1	34	7.65	13.70	1	87.02	LT	784.16	1.3	4
BUSINESS US 24 (McCLUGGAGE RD.)																	
10	STA. 494+07.96	64.61	RT	VANE	789.30	786.30		1	43	4.53		1	111.34	RT	784.08	1.3	4
TOTALS							8	2	272		53	10				13.3	40

MISCELLANEOUS ITEMS							
LOCATION	ENGINEER'S FIELD OFFICE, TYPE A	MOBILIZATION	TRAFFIC CONTROL AND PROTECTION, STD 701422	TRAFFIC CONTROL AND PROTECTION, STD 701701	CHANGEABLE MESSAGE SIGN	CONSTRUCTION LAYOUT	TRAFFIC CONTROL SURVEILLANCE
	CAL MO	L SUM	L SUM	L SUM	CAL MO	L SUM	CAL DAY
ENTIRE JOBSITE	2	1	1	1	1	1	5
TOTALS	2	1	1	1	1	1	5

LOCATION	MANHOLE TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID
	EACH
IL 8 STA 283+76	1
TOTAL	1