

SCHEDULE OF QUANTITIES																											
ACTUAL MEASUREMENTS																											
SN	ROUTE CARRIED	FEATURE CROSSED	SIMS INFORMATION		DECK			APPROACH SLABS					PARAPETS (HUB, FACE & TOP)				TYPE B CURB (FACE & TOP)			GRAND TOTAL (SQ YD)	GRAND TOTAL (SQ FT)	RURAL	URBAN				
			LENGTH	WDTH	LENGTH (E-E)	WIDTH (F-F)	TOTAL AREA (SY)	TOTAL LENGTH (FT)	LENGTH INSIDE PARAPET (FT)	WIDTH INSIDE PARAPET (FT)	LENGTH BEYOND PARAPET (FT)	WIDTH BEYOND PARAPET (O-O)	TOTAL AREA (SY)	HEIGHT	LENGTH		TOTAL AREA (SY)	HEIGHT	LENGTH					TOTAL AREA (SY)			
														3.6 FT TYPICAL	ALONG DECK (FT)	ALONG APPR. (FT)		9 INCH TYPICAL	ALONG APPR. PVT.								

MCLEAN COUNTY STRUCTURES																										
057-0022	I-55 NW BLOOMINGTON	I-74	177.8	79.1	175.5	75.9	1479.8	30.0	30	75.9	0.0	79.1	506.0	3.60	175.5	30.0	188.4	0.75	0.0	0.0	2175.0	19575.0			X	
057-0023	I-55 NW BLOOMINGTON	I-74	177.8	68.0	175.5	64.8	1263.4	30.0	30	64.8	0.0	68.0	432.0	3.60	175.5	30.0	188.4	0.75	0.0	0.0	1884.0	16956.0			X	
057-0024	I-55 NB& CD#2284	US 51B N NORMAL	208.6	52.7	206.3	77.6	1778.5	30.0	30	77.6	0.0	52.7	517.3	3.60	206.3	30.0	213.0	0.75	0.0	0.0	2509.0	22581.0			X	
057-0025	I-55 SB & CD#2287	US 51B N NORMAL	208.6	52.7	206.3	118.8	2722.8	30.0	30	118.8	0.0	52.7	792.0	3.60	206.3	30.0	426.0	0.75	0.0	0.0	3941.0	35469.0			X	
057-0035	FAS 294/OLD 66A NB	MACKINAW RIVER	204.0	33.8	202.3	31.5	708.1	40.0	0	31.5	40.0	31.5	280.0	4.50	202.3	0.0	202.3	0.75	30.0	10.0	1201.0	10809.0	X			
057-0056	OLD US 51	KICKAPOO CREEK			0.0	0.0	0.0	0.0	0	0.0	0.0	0.0	0.0	3.60	0.0	0.0	0.0	0.75	0.0	0.0	0.0	0.0	0.0	X		
057-0063	I-55 BUSN LOOP	US 51AT BLOOMINGTON	167.0	59.5	163.7	56.0	1018.6	20.0	20	56.0	0.0	59.5	248.9	3.60	163.7	20.0	163.0	0.50	163.7	36.4	1467.0	13203.0			X	
057-0064	I-55 BUSN LOOP	CON-RAIL CORP. RR	306.0	59.5	303.2	56.0	1886.6	10.0	10	56.0	0.0	59.5	124.4	3.60	303.2	10.0	258.6	0.50	303.2	67.4	2337.0	21033.0			X	
057-0069	I-55 BUSN LOOP	OLD RT 66/ICG RR	442.0	86.9	436.9	83.7	4063.2	20.0	12	83.7	8.0	86.9	377.7	3.60	436.9	12.0	368.7	1.00	8.0	3.6	4814.0	43326.0			X	
057-0152	I-55 SB	US 24/FAP 317	187.0	46.6	184.7	43.4	890.5	30.0	0	43.4	30.0	45.0	300.0	3.60	184.7	0.0	147.7	0.75	30.0	10.0	1349.0	12141.0	X			
057-0153	I-55 NB	US 24/FAP 317	187.0	53.9	184.7	50.7	1040.3	30.0	0	50.7	30.0	52.2	348.0	3.60	184.7	0.0	147.7	0.75	30.0	10.0	1547.0	13923.0	X			
057-0154	I-55 SB	US 136/FAP 315	216.5	42.0	217.3	40.0	965.8	20.0	12	40.0	8.0	42.0	181.3	3.60	217.3	12.0	193.0	0.75	8.0	2.7	1343.0	12087.0	X			
057-0155	I-55 NB	US 136/FAP 315	216.5	41.8	214.2	40.0	951.9	20.0	12	40.0	8.0	41.8	181.0	3.60	214.2	12.0	190.5	0.75	8.0	2.7	1327.0	11943.0	X			
057-0157	I-55 SB	RAMPS & CH36	241.5	41.7	237.8	38.5	1017.3	20.0	12	38.5	8.0	40.0	173.8	3.60	237.8	12.0	209.4	0.75	8.0	2.7	1404.0	12636.0	X			
057-0158	I-55 NB	RAMPS & CH36	241.5	51.7	241.8	50.0	1343.3	20.0	12	50.0	8.0	51.5	224.9	3.60	241.8	12.0	212.6	0.75	8.0	2.7	1784.0	16056.0	X			
057-0159	I-55 SB	TIMBER CR	196.0	42.0	192.2	38.5	822.2	30.0	30	40.0	0.0	42.0	266.7	3.60	192.2	30.0	201.8	0.75	0.0	0.0	1291.0	11619.0	X			
057-0160	I-55 NB	TIMBER CR	196.0	42.0	192.2	38.5	822.2	30.0	30	40.0	0.0	42.0	266.7	3.60	192.2	30.0	201.8	0.75	0.0	0.0	1291.0	11619.0	X			
057-0163	I-55 SB	MONEY CREEK	193.0	41.8	191.5	38.5	819.2	30.0	0	38.5	0.0	41.8	0.0	3.60	191.5	0.0	153.2	0.75	0.0	0.0	973.0	8757.0	X			
057-0164	I-55 NB	MONEY CREEK	193.0	41.8	191.5	38.5	819.2	30.0	0	38.5	0.0	41.8	0.0	3.60	191.5	0.0	153.2	0.75	0.0	0.0	973.0	8757.0	X			
057-0167	I-55 SB	MACKINAW RIVER	333.0	41.8	330.7	38.5	1414.5	20.0	20	40.0	0.0	40.0	177.8	3.60	330.7	20.0	296.5	0.75	0.0	0.0	1889.0	17001.0	X			
057-0168	I-55 NB	MACKINAW RIVER	333.0	41.9	330.7	38.5	1414.5	20.0	20	40.0	0.0	40.0	177.8	3.60	330.7	20.0	296.5	0.75	0.0	0.0	1889.0	17001.0	X			
057-0169	I-55 SB	TURKEY CREEK	256.3	42.0	253.0	38.5	1082.3	30.0	12	38.5	18.0	42.0	270.7	3.60	253.0	12.0	221.6	0.75	0.0	0.0	1575.0	14175.0	X			
057-0170	I-55 NB	TURKEY CREEK	256.3	42.0	253.0	38.5	1082.3	30.0	12	38.5	18.0	42.0	270.7	3.60	253.0	12.0	221.6	0.75	0.0	0.0	1575.0	14175.0	X			
057-0173	I-55 SB	TURKEY CREEK	97.0	42.0	94.5	38.5	404.3	40.0	12	38.5	28.0	40.0	351.6	3.60	94.5	12.0	94.8	0.75	28.0	9.3	860.0	7740.0	X			
057-0174	I-55 NB	TURKEY CREEK	97.0	42.0	94.5	38.5	404.3	40.0	12	38.5	28.0	40.0	351.6	3.60	94.5	12.0	94.8	0.75	28.0	9.3	860.0	7740.0	X			
057-0178	I-55 SB	A.T. & S.F. RR	147.0	42.0	144.7	38.5	618.9	30.0	12	38.5	18.0	40.0	262.7	3.60	144.7	12.0	134.9	0.75	18.0	6.0	1023.0	9207.0	X			
057-0179	I-55 NB	A.T. & S.F. RR	147.0	42.0	144.7	38.5	618.9	30.0	12	38.5	18.0	40.0	262.7	3.60	144.7	12.0	134.9	0.75	18.0	6.0	1023.0	9207.0	X			
057-0182	I-55 SB	TURKEY CREEK	182.0	41.8	179.7	38.5	768.6	40.0	10	38.5	30.0	41.8	364.2	3.60	179.7	10.0	159.7	0.75	30.0	10.0	1303.0	11727.0	X			
057-0183	I-55 NB	TURKEY CREEK	182.0	41.9	179.7	38.5	768.6	40.0	10	38.5	30.0	41.9	364.9	3.60	179.7	10.0	159.7	0.75	30.0	10.0	1304.0	11736.0	X			
057-0196	US 51SB	KICKAPOO CREEK	288.5	43.2	286.2	40.0	1271.9	30.0	12	40.0	18.0	24.0	202.7	3.60	286.2	12.0	248.1	0.75	18.0	6.0	1729.0	15561.0	X			
057-0197	US 51NB	KICKAPOO CREEK	288.5	43.2	286.2	40.0	1271.9	30.0	12	40.0	18.0	24.0	202.7	3.60	286.2	12.0	248.1	0.75	18.0	6.0	1729.0	15561.0	X			
057-0198	FAP 412 US 51(SB)	US 136	173.7	43.1	171.4	40.0	761.6	10.0	0	40.0	10.0	41.2	91.6	3.60	171.4	0.0	137.1	0.75	10.0	3.3	994.0	8946.0	X			
057-0199	FAP 412 US 51(NB)	US 136	173.7	43.1	171.4	40.0	761.6	10.0	0	40.0	10.0	41.2	91.6	3.60	171.4	0.0	137.1	0.75	10.0	3.3	994.0	8946.0	X			
057-0203	I-39/US 51	MACKINAW RIVER	431.7	93.1	429.4	87.8	4188.7	30.0	12	87.8	18.0	91.0	598.1	3.60	429.4	244.0	733.9	0.00	18.0	0.0	5521.0	49689.0	X			
057-0205	I-39/US 51NB	FAS 472 CH 12	169.9	43.1	167.6	40.0	744.8	30.0	0	40.0	30.0	43.1	287.3	3.60	167.6	0.0	134.1	1.00	30.0	6.7	1173.0	10557.0	X			
057-0206	I-39/US 51SB	FAS 472 CH 12	169.8	43.1	167.5	40.0	744.3	30.0	0	40.0	30.0	43.1	287.3	3.60	167.5	0.0	134.0	1.00	30.0	6.7	1173.0	10557.0	X			

* VARIOUS
 ** FY2012 BRIDGE DECK SEALING
 *** CHAMPAIGN, DEWITT, & MCLEAN

FILE NAME =	USER NAME = ppersonbr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw_work\p\pidot\ppersonbr\d0286468\0570917-shit-schedule.dgn		DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	17	13
		CHECKED -	REVISED -		CONTRACT NO. 70917								
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								