

SCHEDULE OF QUANTITIES																										
ACTUAL MEASUREMENTS																										
SN	ROUTE CARRIED	FEATURE CROSSED	SIMS INFORMATION		DECK			APPROACH SLABS					PARAPETS (HUB, FACE & TOP)				TYPE B CURB (FACE & TOP)			GRAND TOTAL (SQ YD)	GRAND TOTAL (SQ FT)	RURAL	URBAN			
			LENGTH	WDTH	LENGTH (E-E)	WIDTH (F-F)	TOTAL AREA (SY)	TOTAL LENGTH (FT)	LENGTH INSIDE PARAPET (FT)	WIDTH INSIDE PARAPET (FT)	LENGTH BEYOND PARAPET (FT)	WIDTH BEYOND PARAPET (O-O)	TOTAL AREA (SY)	HEIGHT	LENGTH		TOTAL AREA (SY)	HEIGHT	LENGTH					TOTAL AREA (SY)		
														3.6 FT TYPICAL	ALONG DECK (FT)	ALONG APPR. (FT)		9 INCH TYPICAL	ALONG APPR. PVT.							

MCLEAN COUNTY STRUCTURES																								
057-0208	I-39/US 51 SB	SIX MILE CREEK	149.8	43.1	147.5	40.0	655.4	30.0	30	40.0	0.0	43.1	266.7	3.60	147.5	0.0	118.0	1.00	0.0	0.0	1041.0	9369.0	X	
057-0209	I-39/US 51 NB	SIX MILE CREEK	149.8	43.1	147.5	40.0	655.4	30.0	30	40.0	0.0	43.1	266.7	3.60	147.5	0.0	118.0	1.00	0.0	0.0	1041.0	9369.0	X	
057-0210	I-39/US 51 SB	TRIB SIX MILE CREEK	70.6	43.1	68.3	40.0	303.4	30.0	30	40.0	0.0	43.1	266.7	3.60	68.3	0.0	54.6	1.00	30.0	13.3	639.0	5751.0	X	
057-0211	I-39/US 51 NB	TRIB SIX MILE CREEK	70.6	43.1	68.3	40.0	303.4	30.0	30	40.0	0.0	43.1	266.7	3.60	68.3	0.0	54.6	1.00	30.0	13.3	639.0	5751.0	X	
057-0214	I-39 RAMP 816 SB	I-55 & CD#2284/2287	272.9	29.3	270.6	26.0	781.6	30.0	12	26.0	18.0	29.3	186.5	3.60	270.6	0.0	216.5	1.00	12.0	5.3	1190.0	10710.0		X
057-0215	I-39 NB	I-55 & CD#2284/2287	274.7	43.3	272.4	40.0	1210.5	30.0	12	40.0	18.0	43.3	279.9	3.60	272.4	0.0	217.9	1.00	12.0	5.3	1714.0	15426.0		X
057-0216	I-39 SB	NORTHTOWN RD TR 201B	154.6	62.0	152.3	61.5	1040.5	30.0	12	61.5	18.0	64.7	422.8	3.60	152.3	0.0	121.8	1.00	12.0	5.3	1591.0	14319.0		X
057-0217	I-39 NB	NORTHTOWN RD TR 201B	154.0	43.1	151.7	40.0	674.1	30.0	12	40.0	18.0	43.1	279.1	3.60	151.7	0.0	121.3	1.00	12.0	5.3	1080.0	9720.0		X
057-0225	SBI-2 (OLD 51)	DITCH	43.1	35.1	42.9	32.0	152.5	20.0	0	32.0	20.0	33.2	147.6	3.60	42.9	0.0	34.3	0.75	20.0	6.7	342.0	3078.0	X	
057-0226	US 51	MACKINAW RIVER	433.7	35.2	428.8	32.0	1524.6	20.0	12	32.0	8.0	35.2	147.9	3.60	428.8	12.0	362.2	0.75	0.0	0.0	2035.0	18315.0	X	
057-0228	I-55 BUSN LP NB & SB	SUGAR CR & BIKE PATH	183.1	132.7	178.8	129.4	2570.7	30.0	12	129.4	18.0	132.7	875.9	3.60	178.8	12.0	162.2	0.75	18.0	6.0	3615.0	32535.0		X
057-0230	US 24/ FAP 317	ROOKS CREEK	157.5	43.1	151.8	40.0	674.7	30.0	12	40.0	18.0	41.2	271.5	3.60	151.8	12.0	140.6	0.75	18.0	6.0	1093.0	9837.0	X	
057-0237	I-55 NB	FAP 704	213.7	72.8	211.4	69.6	1634.6	30.0	12	69.6	18.0	70.8	468.8	3.60	211.4	12.0	188.3	0.75	18.0	6.0	2298.0	20682.0		X
057-0238	I-55 SB	FAP 704	215.3	64.9	213.0	61.7	1460.0	30.0	12	61.7	18.0	62.9	416.1	3.60	213.0	12.0	189.6	0.75	18.0	6.0	2072.0	18648.0		X
057-0239	FAU 6348/OLD RT66	MONEY CREEK	124.7	33.8	124.7	31.5	436.5	30.0	0	31.5	30.0	31.5	210.0	3.60	124.7	0.0	99.8	0.75	30.0	10.0	757.0	6813.0	X	

MCLEAN TOTALS (SQ FT):																					732,339	438,156	294,183
GRAND TOTALS (SQ FT):																					1,055,727	651,060	404,667

* VARIOUS
 ** FY2012 BRIDGE DECK SEALING
 *** CHAMPAIGN, DEWITT, & MCLEAN