

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE							
				ROADWAY	PARKING LANES				SIDEWALK		
				80% FEDERAL 20% STATE	50% STATE / 50% VILLAGE 11' -6" TO 23' -6"		100% VILLAGE 23' -6"+		100% STATE	100% VILLAGE OF MODESTO	80% STATE 20% VILLAGE OF MODESTO
					MODESTO	PALMYRA	MODESTO	PALMYRA			
				0005				0021			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45	43.9	0.3	0.5	0.1	0.2			
40600300	AGGREGATE (PRIME COAT)	TON	225.5	220.1	1.5	2.8	0.3	0.8			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4525	4525							
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	60	60							
40600990	TEMPORARY RAMP	SQ YD	807	807							
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	10195	9971	65.3	118.2	9.7	30.8			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	640	640							
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3069						1490		1579
42400800	DETECTABLE WARNINGS	SQ FT	494						302		192
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	8624	5956	777	1408	116	367			
44000400	GUTTER REMOVAL	FOOT	101	101							
44000600	SIDEWALK REMOVAL	SQ FT	2241						1193		1048
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SQ YD	25	25							

FILE NAME =	USER NAME = mortyj	DESIGNED -	REVISED 01/31/2012
c:\pwwork\pwwork\mortyj\0264327\067	E48-sh1-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = Jan-31-2012 10:04:49AM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET	OF	SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
608	120RS-2 & 121 RS-4	MACOUPIN	69	4
			CONTRACT NO. 72E48	
ILLINOIS FED. AID PROJECT				