

PAVING SCHEDULE			LENGTH	AVERAGE PAVEMENT WIDTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	LEVELING BINDER (MACHINE METHOD), N70	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP	EXCAVATING AND GRADING EXISTING SHOULDERS
STATION	TO	STATION	FOOT	FOOT	SO YD	SO YD	SO YD	SO YD	SO YD	GALLON	TON	TON	TON	TON	SO YD	UNIT
5+06.00	TO	5+41.00	35.0	18.0	70.0	70.0	0.0	0.0	0.0	7.0	0.1	6.7	1.5	2.7	10.0	0.7
5+41.00	TO	43+99.00	3858.0	18.0	7716.0	0.0	0.0	7716.0	0.0	771.6	15.4	738.1	324.1	298.8	0.0	77.2
43+99.00	TO	44+49.00	50.0	18.0	100.0	0.0	0.0	0.0	100.0	10.0	0.2	9.6	4.2	3.9	0.0	1.0
44+99.00	TO	50+86.00	587.0	18.0	1174.0	0.0	0.0	0.0	1174.0	117.4	2.3	98.6	49.3	0.0	15.0	0.0
50+86.00	TO	52+61.00	175.0	18.0	350.0	BRIDGE OMISSION										
52+61.00	TO	58+16.00	555.0	18.0	1110.0	0.0	0.0	0.0	1110.0	111.0	2.2	93.2	46.6	0.0	15.0	0.0
58+16.00	TO	59+90.00	174.0	21.0	406.0	0.0	0.0	0.0	406.0	40.6	0.8	34.1	17.1	0.0	0.0	0.0
59+90.00	TO	60+40.00	50.0	21.0	116.7	0.0	0.0	0.0	116.7	11.7	0.2	9.8	4.9	3.9	0.0	0.0
60+40.00	TO	62+22.00	182.0	21.0	424.7	0.0	0.0	424.7	0.0	42.5	0.8	35.7	17.8	14.1	0.0	0.0
62+22.00	TO	73+78.00	1156.0	18.0	2312.0	0.0	0.0	2312.0	0.0	231.2	4.6	221.2	97.1	87.2	0.0	23.1
73+78.00	TO	73+98.00	20.0	18.0	40.0	0.0	0.0	40.0	0.0	4.0	0.1	3.9	1.7	3.9	0.0	0.4
73+98.00	TO	74+79.00	81.0	18.0	162.0	0.0	0.0	0.0	0.0	16.2	0.3	15.5	9.1	6.3	0.0	1.6
74+79.00	TO	79+50.00	471.0	20.0	1046.7	0.0	0.0	0.0	0.0	104.7	2.1	87.9	58.6	36.5	0.0	0.0
79+50.00	TO	79+85.00	35.0	20.0	77.8	0.0	77.8	0.0	0.0	7.8	0.2	6.5	1.7	2.7	10.0	0.0
TOTALS			7429.0		15106.0	70	78	10493	2907	1476	29	1361	634	460	50.0	104

PAVEMENT MARKING SCHEDULE							
LOCATION			LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING-LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING-LINE 4"
STATION	TO	STATION	FOOT	FOOT	FOOT	SO FT	FOOT
OLD US 40							
5+06.00	TO	12+20.00	714.0	285.6	2,320.5	23.6	2,320.5
12+20.00	TO	32+33.00	2,013.0	805.2	4,529.3	66.4	4,529.3
32+33.00	TO	42+62.00	1,029.0	411.6	3,344.3	34.0	3,344.3
42+62.00	TO	61+55.00	1,893.0	757.2	7,438.0	62.5	7,438.0
61+55.00	TO	72+47.00	1,092.0	436.8	3,549.0	36.0	3,549.0
72+47.00	TO	79+85.00	738.0	295.2	1,558.5	24.4	1,558.5
SHEET TOTALS			7,479	2,992	22,740	247	22,740

PATCHING SCHEDULE					
CLASS D PATCHES, TYPE 1, 13"	CLASS D PATCHES, TYPE 11, 13"	CLASS D PATCHES, TYPE 111, 13"	CLASS D PATCHES, TYPE 1V, 13"	PARTIAL DEPTH REMOVAL (VAR. DEPTH)	HOT-MIX ASPHALT FOR PATCHING
445 SQ. YD.	455 SQ. YD.	147 SQ. YD.	108 SQ. YD.	*750 SQ. YD.	*210 TON

\* PATCH CENTERLINE STA. 74+05 TO STA. 79+85  
 PATCH CRACK (5' FROM CENTERLINE) BOTH LANES  
 STA. 61+95 TO STA. 74+05  
 ADDITIONAL SMALL ISOLATED PATCHES