

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
Z0049799	PROTECTING OR RESETTING SURVEY MARKERS	EACH	3	3		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2614	2614		
40600300	AGGREGATE (PRIME COAT)	TON	52	52		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	538	538		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	311	311		
40600990	TEMPORARY RAMP	SO YD	75	75		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1094	1094		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	13131	13131		
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SO YD	8	8		
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	72	72		
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	43	43		
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	551	551		
67100100	MOBILIZATION	L SUM	1	1		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1436	1436		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	239	239		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	117	117		
X4060995	TEMPORARY RAMP, SPECIAL	SO YD	500	500		
* X7801000	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	108	108		
* X7801004	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7357	7357		
* X7801006	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	147	147		
* X7801012	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	390	390		
* X7801024	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	75	75		
Z0070202	SURVEY MARKER VAULT	EACH	3	3		

*SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -
#FILE#		DRAWN -	REVISED -
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -
	PLOT DATE = #DATE#	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	72 RS-2	EFFINGHAM	14	3
CONTRACT NO. 74541				
ILLINOIS FED. AID PROJECT				