

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FED. 20% STATE 0011			
20200100	EARTH EXCAVATION	CU YD	1880	1880			
* 25000200	SEEDING, CLASS 2	ACRE	1	1			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90			
* 25100115	MULCH, METHOD 2	ACRE	3	3			
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	8	8			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200			
28000305	TEMPORARY DITCH CHECKS	FOOT	153	153			
28000500	INLET AND PIPE PROTECTION	EACH	2	2			
28001000	AGGREGATE (EROSION CONTROL)	TON	7	7			
28100107	STONE RIPRAP, CLASS A4	SQ YD	1245	1245			
28200200	FILTER FABRIC	SQ YD	1245	1245			
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	413	413			

\*SPECIALTY ITEM

FILE NAME = #FILEL#	USER NAME = Paul	DESIGNED - JLS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE. 327	SECTION 20BR	COUNTY CLINTON	TOTAL SHEETS 51	SHEET NO. 3
	PLOT SCALE = 40.0000' / IN.	DRAWN - PDB	REVISED -		SCALE:	SHEET NO. 1 OF 5 SHEETS	STA.	TO STA.	CONTRACT NO. 76B43			
	PLOT DATE = 11/17/2011	CHECKED - BRM	REVISED -		FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT							