

SUMMARY OF QUANTITIES

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | |
|-----------------------|---|-------|------------------|---|---|
| CODE NO | ITEM | UNIT | | ST. CLAIR 80% FED 20% STATE 0005 | CLINTON 80% FED 20% STATE 0005 |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 44 | 26.1 | 17.9 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 207 | 126 | 81 |
| 40600645 | LEVELING BINDER (MACHINE METHOD), N90 | TON | 3521.1 | 2149.1 | 1372 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 0.5 | 0.5 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 1120 | 400 | 720 |
| 40600990 | TEMPORARY RAMP | SQ YD | 70 | 40 | 30 |
| 40603345 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 | TON | 7042.2 | 4298.4 | 2743.8 |
| 44000155 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | SQ YD | 137838.1 | 84024.6 | 53813.5 |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 174.4 | | 174.4 |
| 44200140 | PAVEMENT PATCHING, TYPE I, 12 INCH | SQ YD | 6 | 3 | 3 |
| 44200144 | PAVEMENT PATCHING, TYPE II, 12 INCH | SQ YD | 393 | 319.6 | 73.4 |
| 44200148 | PAVEMENT PATCHING, TYPE III, 12 INCH | SQ YD | 111 | 111 | |
| 44200150 | PAVEMENT PATCHING, TYPE IV, 12 INCH | SQ YD | 2060 | 1964 | 96 |

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | |
|-----------------------|---|--------|------------------|---|---|
| CODE NO | ITEM | UNIT | | ST. CLAIR 80% FED 20% STATE 0005 | CLINTON 80% FED 20% STATE 0005 |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 1773 | 988 | 785 |
| 48203100 | HOT-MIX ASPHALT SHOULDERS | TON | 4477 | 2760 | 1717 |
| 50105220 | PIPE CULVERT REMOVAL | FOOT | 45 | | 45 |
| 542D1069 | PIPE CULVERTS, CLASS D, TYPE 2 24" | FOOT | 45 | | 45 |
| 60107600 | PIPE UNDERDRAINS 4" | FOOT | 1162 | 1162 | |
| * 63000003 | STEEL PLATE BEAM GUARDRAIL, TYPE A. 9 FOOT POSTS | FOOT | 1045 | 1045 | |
| * 63100089 | TRAFFIC BARRIER TERMINAL, TYPE 6B | EACH | 4 | 4 | |
| * 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 4 | 4 | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 1130 | 1130 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 4 | 2 |
| 67100100 | MOBILIZATION | L SUM | 1 | 0.81 | 0.19 |
| 70100310 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701421 | L SUM | 1 | | 1 |

*SPECIALTY ITEM

| | | | |
|--|-----------------------------|------------|-----------|
| FILE NAME = | USER NAME = milleraj | DESIGNED - | REVISED - |
| ca:\pwork\pvidot\milleraj\d0119358\d87 | 881-sht-planB.dgn | DRAWN - | REVISED - |
| | PLOT SCALE = 100.0000 / in. | CHECKED - | REVISED - |
| | PLOT DATE = 12/23/2011 | DATE - | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

| | | | |
|------------------------------|---------------------|------|---------|
| SUMMARY OF QUANTITIES | | | |
| SCALE: | SHEET NO. OF SHEETS | STA. | TO STA. |

| | | | | |
|---------------------|-------------------|--------|---------------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 327 | (82-11,14-12)RS-1 | • | 64 | 3 |
| FED. ROAD DIST. NO. | | | ILLINOIS FED. AID PROJECT | |
| CONTRACT NO. 76B81 | | | | |

• ST. CLAIR / CLINTON