

SUMMARY OF QUANTITIES

URBAN

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80%_FED 20%_STATE 0005		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.3	7.3		
40600300	AGGREGATE (PRIME COAT)	TON	35.2	35.2		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	986	986		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	468	468		
40600990	TEMPORARY RAMP	SQ YD	78	78		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1972	1972		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.02	0.02		
40800030	AGGREGATE (PRIME COAT)	TON	0.9	0.9		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	6	6		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	28112	28112		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	236	236		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	586	586		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80%_FED 20%_STATE 0005		
67100100	MOBILIZATION	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5024	5024		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28600	28600		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9534	9534		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28600	28600		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	330	330		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	330	330		

*SPECIALTY ITEM

FILE NAME =	USER NAME = millerra	DESIGNED -	REVISED -
et\pwork\pwork\millerra\d0203339\d076e28-aht-plan.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	64-IRS-4	ST. CLAIR	23	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 76E28	