

RESURFACING SCHEDULE										
STA.	TO	STA.	LENGTH	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURFACE REMOVAL 1 1/2"	POLY-LEVEL BINDER (MM), N50, 3/4"	HMA SURFACE COURSE, MIX D, 1 1/2"	HMA SHOULDERS 2 1/4"	AGGREGATE WEDGE SHOULDERS
				(TON)	(TON)	(SQ YD)	(TON)	(TON)	(TON)	(TON)
228+00.	TO	272+00	4400	7.3	35.2	28112	986	1972	586	236
TOTAL:				7.3	35.2	28112	986	1972	586	236

THERMOPLASTIC PAVEMENT MARKINGS SCHEDULE									
STA.	TO	STA.	LENGTH	4"			RAISED REFLECTIVE PAVEMENT MARKERS		
				WHITE		DOUBLE YELLOW	AMBER ONE-WAY	CRYSTAL ONE-WAY	REMOVAL
				SKIP DASH	LANE LINE	LANE LINE			
(FEET)	(FEET)	(FEET)	(FEET)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	
228+00.	TO	272+00.	4400	2200	8800	17600	220	110	330
TOTAL:				28600			330	330	

SIDEROAD/BUTT JOINT SCHEDULE									
STA.	TO	STA.	L/R	WIDTH	INCIDENTAL HMA SURFACING	BIT. MAT. (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMPORARY RAMP	BUTT JOINTS
				(FEET)	(SQ YD)	(TON)	(TON)	(SQ YD)	(SQ YD)
228+00.00				48				26.7	160
FUTURA PLAZA									
232+26.13			L	48	6	0.02	0.9	26.7	146.7
272+00.00				48				24.4	160
TOTAL:					6	0.02	0.9	78	468