L25E | L20E

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005			
				US 40 RURAL	US 40 URBAN	IL 127 URBAN	
CODE NO	ITEM	UNIT		80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	50% CITY 50% STATE
				L25ED	L20EM	L20EL	07COL
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	299	164	135		
20400800	FURNISHED EXCAVATION	CU YD	540	420	120		
*25000200	SEEDING, CLASS 2	ACRE	0.75	0.58	0.17		
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68	53	15		
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68	53	15		
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68	53	15		
*25100115	MULCH, METHOD 2	ACRE	0.75	0.58	0.17		
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	222		222		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27.9	13.66	12.74	1.4	0.1
40600300	AGGREGATE (PRIME COAT)	TON	135	66	61	7	1
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1738	917	821		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	782	37	745		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	100	20	80		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005			
				US 40 RURAL	US 40 URBAN	IL 127 URBAN	
CODE NO	ITEM	UNIT		80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	50% CITY 50% STATE
				L25ED	L20EM	L20EL	07COL
40600990	TEMPORARY RAMP	SQ YD	170	12	12	146	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	3684	1849	1657	168	10
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	55	3	52		
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	38221	20005	18216		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2115			1996	119
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	377	138	239		
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	81		81		
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	92		92		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	27601	16368	11233		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	775	425	350		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	3004	1819	1185		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	951		951		
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1874	1312	562		

*SPECIALTY ITEM

FILE NAME = c:\pw_work\pwidot\dintelmanjn1\d0260347\d876a95-sht-plan.dgn	USER NAME = dintelmanjn	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/5/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
779/42	(36-2)RS-3,139-1RS-2	BOND	16	3
		CONTRACT NO. 76E95		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		