

GUARDRAIL SCHEDULE

LOCATION		SPBGR, TYPE A 6' POSTS	LONG-SPAN GUARDRAIL OVER CULVERT, 12'-6''	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKERS	FURNISHED EXCAVATION	COMMENTS
MILE PT.	EB/WB	FOOT	FOOT	EACH	(EACH)	(EACH)	CU YD	
0.13	EB	137.5		1	1	3	30	6'X6' BOX STR. 2431
0.185	EB		162.5			4		
0.20	EB	50		1	1	1	30	
0.49	EB	137.5		1	1	3	30	4'X3' BOX
0.512	EB		162.5			4		
0.53	EB	50		1	1	1	30	
0.49	WB	50		1	1	1	30	
0.512	WB		162.5			4		
0.53	WB	137.5		1	1	4	30	
0.81	EB	137.5		1	1	3	30	10'X6' BOX STR. 2432
0.841	EB		162.5			4		
0.85	EB	50		1	1	1	30	
0.89	EB	137.5		1	1	3	30	5'X3' BOX
0.911	EB		162.5			4		
0.93	EB	50		1	1	1	30	
0.89	WB	50		1	1	1	30	
0.911	WB		162.5			4		
0.93	WB	137.5		1	1	3	30	
1.36	EB	137.5		1	1	3	30	4'X6' BOX
1.376	EB		162.5			4		
1.40	EB	50		1	1	1	30	
1.53	EB	137.5		1	1	3	30	5'X6' BOX
1.606	EB		162.5			4		
1.57	EB	50		1	1	1	30	
2.30	EB	137.5		1	1	3	30	4'X6' BOX
2.497	EB		162.5			4		
2.70	EB	187.5				5		
2.563	EB		162.5			4		10'X9' BOX STR. 2433
2.60	EB	50		1	1	1	30	
TOTALS		1875	1625	18	18	86	540	

SEE GUARDRAIL DETAILS PAGE 14

FILE NAME =	USER NAME = dntelmonjn	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pwork\pwork\dot\dntelmonjn\1\0260347	d876e95-shr-plan.dgn	DRAWN -	REVISED -			779/42	(36-2)RS-3,139-1RS-2	BOND	16	11	
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -			CONTRACT NO. 76E95					
	PLOT DATE = 12/14/2011	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO
						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					