

INDEX OF SHEETS

- 1 COVER SHEET
- 2 GENERAL NOTES, STANDARDS, INDEX OF SHEETS, COMMITMENTS
- 3 SUMMARY OF QUANTITIES
- 4 LOCATION MAP
- 5-8 EXISTING STRUCTURE PLANS - LOCATION 1 - SN 014-0054
- 9-12 EXISTING STRUCTURE PLANS - LOCATION 2 - SN 014-0065

COMMITMENTS

NONE

GENERAL NOTES

- 1 LOCATION 1: SN 014-0054, LOCATED AT ST. ROSE ROAD OVER U.S. ROUTE 50, NEAR BREESE
  - 2 LOCATION 2: SN 014-0065, LOCATED AT IL ROUTE 160 OVER U.S. ROUTE 50, IN TRENTON
  - 3 AT LOCATIONS 1 & 2: CLEANING AND PAINTING OF THE EXISTING STRUCTURAL STEEL AND BEARINGS SHALL BE AS SPECIFIED IN THE SPECIAL PROVISION FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES." ALL EXISTING STEEL AND BEARINGS SHALL BE CLEANED PER "NEAR WHITE BLAST CLEANING -SSPC-SP10." ALL EXISTING STEEL AND BEARINGS SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF "PAINT SYSTEM 1-OZ/E/U." THE COLOR OF THE FINAL FINISH COAT FOR ALL STRUCTURAL STEEL SURFACES AND BEARINGS SHALL BE GREY MUNSELL NO. 5B 7/1.
  - 4 A MINIMUM OF TWO AIR MONITORS WILL BE REQUIRED AT LOCATION 1, AND A MINIMUM OF ONE AIR MONITOR WILL BE REQUIRED AT LOCATION 2 TO MONITOR ABRASIVE BLASTING OPERATION AT EACH BRIDGE. SEE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES."
  - 5 THE SSPC-QP1 AND SSPC-QP2 CERTIFICATIONS WILL BE REQUIRED FOR ALL BRIDGES.
  - 6 ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
    - AT&T ILLINOIS
    - CHARTER COMMUNICATIONS, INC
    - CLINTON COUNTY ELECTRIC COOPERATIVE, INC.
    - ST. ROSE PUBLIC WATER DISTRICT
    - CITY OF TRENTON
    - TRI-TOWNSHIP WATER DISTRICT
- MEMBERS OF J.U.L.I.E. CALL TOLL FREE (800) 892-0123 OR 811 AND ARE INDICATED BY \*.  
NON- J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
- 7 ONE (1) ADDITIONAL "ROAD CONSTRUCTION AHEAD" (WITH ARROW) SIGN SHALL BE REQUIRED FOR THE ENTRANCE/EXIT RAMP FROM ST. ROSE ROAD. THE COST SHALL BE INCLUDED IN THE PAY ITEM "TRAFFIC CONTROL AND PROTECTION, STANDARD 701201."
  - 8 ALL TURF AREAS DISTURBED BY THE CONTRACTOR SHALL BE SEEDED WITH THE APPROPRIATE EROSION CONTROL AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.
  - 9 ANY ADDITIONAL FLAGGER NEEDED FOR THE ENTRANCE/EXIT RAMP FROM ST. ROSE ROAD SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04.

STANDARDS

- 000001-06
- 701001-02
- 701006-03
- 701101-02
- 701106-02
- 701201-04
- 701422-04
- 701901-02

FILE NAME =	USER NAME = challandeske	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES, STANDARDS, INDEX OF SHEETS, COMMITMENTS</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
o:\pwwork\pwwork\challandeske\d0287012	0876F43-sh1-gennote.dgn	DRAWN -	REVISED -			327/690	14-14HB-P, 14-12BR-P	CLINTON	12	2	
	PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -			CONTRACT NO. 76F43					
	PLOT DATE = 12/23/2011	DATE -	REVISED -			SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	