GENERAL NOTES

- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 2 ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

UTILITY	ABOVE	BELOW
	GROUND	GROUND
* BOND MADISON WATER COMPANY		X
* CHARTER COMMUNICATIONS, INC.		X
* FRONTIER NORTH, INC COMMUNICATIONS	X	X
* VILLAGE OF GRANTFORK - WATER & SEWER		X
* CITY OF HIGHLAND - WATER, SEWER & ELECTRIC		X
* CHARTER COMMUNICATIONS, INC CABLE TV	X	

MEMBERS OF J.U.L.I.E. CAN CALL TOLL FREE (800)-892-0123 OR 811 AND ARE INDICATED BY "*". NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

THE ILLINOIS DEPARTMENT OF TRASPORTATION STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB-CONTRACTORS TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERALLY FUNDED HIGHWAY CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORKFORCE AND TRAINEE GOALS. THIS PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGWAY CONSTRUCTION-RELATED SKILLS, E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSEWORK (CARPENTRY, CONCRETE FLATWORK, BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION, TO PREPARE THEM FOR A CAREER IN THE HIGHWAY CONSTRUCTION TRADES. GRADUATES ARE WELL-TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEVEL CONSTRUCTION WORKERS. PLEASE CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCTP COORDINATOR AT 618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE AND TRAINEE GOALS.

COMMITMENTS

NONE

SUMMARY OF QUANTITIES

	SUMMARY OF QUANTITIES	URBAN	100% STATE	TRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	5450	5450	
42400800	DETECTABLE WARNINGS	SQ FT	116	116	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	407	407	
44000600	SIDEWALK REMOVAL	SQ FT	5450	5450	
60604400	COMBINATION CONCRETE CURB AND GUTTER,	FOOT	407	407	
	TYPE B-6.18				
67100100	MOBILIZATION	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION STADARD 701801	L SUM	1	1	
***************************************		,			

FILE NAME =	USER NAME = burnsideem	DESIGNED -	REVISED ~	Γ
c:\pw_work\pwidot\burnsideem\d0287054\d	376f46-sht-plan.dgn	DRAWN -	REVISED ~	1
	PLOT SCALE = 100.0000 '/ in.	CHECKED ~	REVISED -	
	PLOT DATE = 12/23/2011	DATE -	REVISED -	l

STATE	0	F ILLINOIS	
EPARTMENT	0F	TRANSPORTATION	

SCALE:

GENERAL NOTES/COMMITMENTS					F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
& SOQ			70	60-13RA-1	MADISON	6	2				
<u> </u>						CONTRACT	NO. 7	6F46			
	SHEET	NO.	OF	SHEETS	STA.	TO STA.		OAD DIST. NO. ILLINOIS FED. A			