

SUMMARY OF QUANTITIES					
CODE NO.	ITEM	CONSTRUCTION TYPE CODE		0003	0021
		UNIT	TOTAL QUANTITY	ROADWAY 80% FEDERAL 20% STATE	SIGNALS 80% FEDERAL 20% STATE
44004250	PAVED SHOULDER REMOVAL	SO YD	9440	9440	
44201019	CLASS B PATCHES, TYPE II, 14 INCH	SO YD	120	120	
44201299	DOWEL BARS 1 1/2"	EACH	300	300	
44213200	SAW CUTS	FOOT	720	720	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	12697	12697	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	917	917	
48203042	HOT-MIX ASPHALT SHOULDERS, 11 1/4"	SO YD	9754	9754	
48300405	PORTLAND CEMENT CONCRETE SHOULDERS, 9 1/4"	SO YD	467	467	
50104400	CONCRETE HEADWALL REMOVAL	EACH	6	6	
50104650	SLOPE WALL REMOVAL	SO YD	239	239	
50105220	PIPE CULVERT REMOVAL	FOOT	53	53	
50800205	REINFORCEMENT BARS, EPOXY COATED	LBS	10160	10160	
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1	1	
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	1	1	
14					

FILE NAME =	USER NAME = kellejkd	DESIGNED -	REVISED -
c:\pwork\puidot\kellejkd\0205725\782	6-shr-misc.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / 1 in.	CHECKED -	REVISED -
	PLOT DATE = 12/16/2011	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET	OF	SHEETS
	STA.	TO	STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	11-4R-1,N-3,TS-3	Williamson	220	8
CONTRACT NO.			78216	
ILLINOIS FED. AID PROJECT				