

| SUMMARY OF QUANTITIES | | | | | |
|-----------------------|---|------------------------|----------------|-------------------------------------|-------------------------------------|
| CODE NO. | ITEM | CONSTRUCTION TYPE CODE | | 0003 | 0021 |
| | | UNIT | TOTAL QUANTITY | ROADWAY 80% FEDERAL 20% STATE | SIGNALS 80% FEDERAL 20% STATE |
| 54002020 | EXPANSION BOLTS, 3/4 INCH | EACH | 28 | 28 | |
| 54003000 | CONCRETE BOX CULVERTS | CU YD | 64.8 | 64.8 | |
| 54010303 | PRECAST CONCRETE BOX CLUVERTS 3' x3' | FOOT | 40 | 40 | |
| 54248510 | CONCRETE COLLAR | CU YD | 2.4 | 2.4 | |
| 542A0220 | PIPE CULVERTS, CLASS A, TYPE 1 15" | FOOT | 6 | 6 | |
| 542A0223 | PIPE CULVERTS, CLASS A, TYPE 1 18" | FOOT | 11 | 11 | |
| 542A0229 | PIPE CULVERTS, CLASS A, TYPE 1 24" | FOOT | 25 | 25 | |
| 542A0235 | PIPE CULVERTS, CLASS A, TYPE 1 30" | FOOT | 11 | 11 | |
| 542A0247 | PIPE CULVERTS, CLASS A, TYPE 1 42" | FOOT | 74 | 74 | |
| 54213660 | PRECAST REINFORCED CONCRETE FLARED END SECTION, 15" | EACH | 2 | 2 | |
| 54213663 | PRECAST REINFORCED CONCRETE FLARED END SECTION, 18" | EACH | 2 | 2 | |
| 54213669 | PRECAST REINFORCED CONCRETE FLARED END SECTION, 24" | EACH | 1 | 1 | |
| 54213687 | PRECAST REINFORCED CONCRETE FLARED END SECTION, 42" | EACH | 4 | 4 | |
| 54215424 | CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24" | EACH | 1 | 1 | |
| 14 | | | | | |

FILE NAME =
c:\pwork\puidot\kellykd\0205725\782

USER NAME = kellykd
6-shr-misc.dgn
PLOT SCALE = 100.0000 / in.
PLOT DATE = 12/16/2011

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

| | | | | |
|--------------------|------------------|------------|---------------------------|--------------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 331 | 01-4R-1,N-3,TS-3 | Williamson | 220 | 9 |
| CONTRACT NO. 78216 | | | ILLINOIS FED. AID PROJECT | |