

PAVEMENT AND SHOULDER SCHEDULE CONTINUED

LOCATION STATION TO STATION	PROCESSING MODIFIED SOIL 12"	LIME	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX E, N105	PORTLAND CEMENT CONCRETE PAVEMENT, 9 1/4" (JOINTED)	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	STRIP REFLECTIVE CRACK CONTROL TREATMENT	TEMPORARY RAMP	PROTECTIVE COAT	AGGREGATE BASE COURSE, TYPE A 8"	HOT-MIX ASPHALT BASE COURSE, 5 1/4"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, N105, IL-19.0	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N70	PCC SIDEWALK, 5"	DETECTABLE WARNING	REMARKS
	SQ YD	TON	SQ YD	TON	SQ YD	GAL	GAL	TON	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	SO FT	SO FT	
GREENBRIAR RD.																			
+31.4 LT TO 1+17.8 LT			232		179						179								NW ISLAND
+32.4 TO 1+17.8			712		712						712								
+33.12 RT TO 1+17.8 RT			420		338						338								NE ISLAND
1+17.8 RT TO 1+92.5 RT	271	7		20		43	43	1				237		30					
1+17.8 LT TO 2+26.14 LT			49																
1+17.8 TO 10+68.09				391		419		7	950	70									
1+92.05 LT TO 5+13.99 LT											179						1610		
1+92.5 RT TO 2+36.38 RT	137	4		10		21	21	1				117		15					
1+95 LT																		10	
2+36.38 RT TO 5+36.38 RT	736	19		50		108	108	4				600		76					
5+08 LT																		20	
5+36.38 RT TO 10+68.09 RT	952	22		60		128	128	4	44			709		89					
5+62.27 LT TO 9+86.74 LT											236						2122		
5+68 LT																		17	
9+40 LT																		12	
10+18 LT																		12	
10+15.35 LT TO 13+01.86 LT											159						1433		
10+68.09 RT TO 11+55.24 RT				7		14	14	0					80		10				
10+71.2 RT TO 11+90.8 RT	141	4																	
12+96 LT																		18	
13+22.7 LT TO 14+41.33 LT											66						593		
13+23 LT																		12	
14+37 LT																		17	
CONESTOGA TRAIL																			
31+60.94 TO 39+46.45						413		7			2414		323		192				
PIN OAK RD.																			
33+23.97 TO 33+49.54							19	0			112		15		9				
33+49.54 TO 35+28.05							94	2			549		74		44				
SUBTOTALS																			
	2238	56	1413	537	1228	733	840	26	950	114	1868	3074	1742	412	220	244	5758	118	

COMBINED TOTALS	4556	114	29167	1188	5345	3822	3373	119	12697	233	6451
------------------------	------	-----	-------	------	------	------	------	-----	-------	-----	------