

## RIGHT-OF-WAY MARKERS

LOCATION STATION	OFFSET FROM CENTERLINE	FURNISH AND ERECTING RIGHT-OF-WAY MARKERS
	FEET	EACH
<b>GREENBRIAR RD.</b>		
1+36.71	100 RT	1
2+25	75 RT	1
4+00	75 RT	1
4+00	60 RT	1
8+00	60 RT	1
8+00	50 RT	1
11+00	50 RT	1
11+00	30.4 RT	1
<b>TOTALS</b>		<b>8</b>

## TREE REMOVAL SCHEDULE

LOCATION STATION	OFFSET FROM CENTERLINE	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TREE REMOVAL, ACRES	REMARKS
	FEET	UNITS	UNITS	ACRE	
<b>ILLINOIS 13 (WB)</b>					
1+02	60 LT	10			
1+05	59 LT	12			
1+13	59 LT	14			
2+14	55 LT	10			
2+21	56 LT	14			
2+32	54 LT	14			
2+47	59 LT	10			
2+61	60 LT	12			
2+73	61 LT	10			
2+87	62 LT		20		
2+91	58 LT	15			
3+23	61 LT	15			
3+32	61 LT	14			
3+42	68 LT	8			
3+52	67 LT	10			
14+69	30 LT	12			
14+69	34 LT	15			
15+00	29 LT	10			
15+10	29 LT	12			
15+38	36 LT	10			
15+50	39 LT	12			
15+72	37 LT	8			
15+84	39 LT	8			
16+11	38 LT	14			
17+08	39 LT	10			
17+28	45 LT	10			
17+68	38 LT		24		
<b>ILLINOIS 13 (EB)</b>					
0+95 RT TO 3+00 RT				0.03	
3+50 RT TO 6+00 RT				0.07	
8+00 RT TO 24+33 RT				0.42	
<b>CONESTOGA TRAIL</b>					
31+61 TO 39+47				0.89	
<b>PIN OAK RD.</b>					
32+28 TO 35+28				0.13	
<b>TOTALS</b>		<b>289</b>	<b>44</b>	<b>1.54</b>	

## EARTHWORK SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
	CU YD	CU YD	CU YD	CU YD	
<b>ILLINOIS 13 (MEDIAN)</b>					
<b>13WBL-2 ALIGNMENT</b>					
393+50 TO 412+00	2706	2030	2072	-43	
413+00 TO 424+00	2099	1574	835	739	
<b>PROPI3WB ALIGNMENT</b>					
0+00 TO 17+87.5	1381	1036	382	654	
<b>13WBL-3 ALIGNMENT</b>					
442+00 TO 448+00	212	159	0	159	
<b>ILLINOIS 13 WB</b>					
<b>13WBL-2 ALIGNMENT</b>					
414+00 TO 416+00	122	92	26	66	
<b>PROPI3WB ALIGNMENT</b>					
0+00 TO 17+87.5	2867	2150	2778	-628	
<b>ILLINOIS 13 EB</b>					
<b>PROPI3EB ALIGNMENT</b>					
0+00 TO 30+00	5422	4067	4141	-75	
<b>GREENBRIAR</b>					
0+50 TO 11+50	1870	1403	416	987	
<b>PIN OAK RD. (EXIST.)</b>					
30+54 TO 31+60.94	35	26	32	-6	
<b>CONESTOGA TRAIL</b>					
31+60.94 TO 39+46.45	2019	1514	549	965	
<b>PIN OAK RD. (PROP.)</b>					
33+38.11 TO 35+28.05	748	561	160	401	
<b>TOTALS</b>		<b>19481</b>	<b>14611</b>	<b>11391</b>	<b>3220</b>

25% Shrinkage Factor for Earth Excavation