



**GIRDER ELEVATION**

"NTR" denotes plates to which notch toughness requirements are applicable.

TOP OF WEB ELEVATIONS				
Girder No.	Centerline S. Abut.	Centerline Pier	Centerline Splice	Centerline N. Abut.
1	909.83	911.63	912.20	916.04
2	909.94	911.74	912.31	916.15
3	910.05	911.85	912.42	916.26
4	909.94	911.74	912.31	916.15
5	909.83	911.63	912.20	916.04

Note: For fabrication only.

**NOTES**

All cross frames or diaphragms shall be installed as steel is erected and secured with erection pins and bolts except as otherwise noted. Individual cross frames or diaphragms at supports may be temporarily disconnected to install bearing anchor rods.

Load carrying components designated "NTR" shall conform to the Supplemental Requirements for Notch Toughness, Zone 2.

DESIGNED	J.A.M.
CHECKED	A.L.S.
DRAWN	S.A.P.
CHECKED	J.A.M. & A.L.S.

<p><b>FEHR-GRAHAM &amp; ASSOCIATES, LLC</b> ENGINEERING AND SCIENCE CONSULTANTS FREEPORT, IL ROCKFORD, IL ROCHELLE, IL MONROE, WI SPRINGFIELD, IL 4440 ASH GROVE SPRINGFIELD, IL 62711 (217)-793-9600 www.fehr-graham.com</p>	C.H.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	9	06-00127-00-BR	JO DAVIESS	55	23
	SCOUT CAMP ROAD			CONTRACT NO. 85539	
ILLINOIS					