

2.464m End-To-End Of Deck

1.043m

150mmx150mm

Treated Timber

Rail Post (Typ.,

CAUTION

OVERHEAD

WIRES

Bk. Of W. . 34+558.71

244.179

1.043m

--189mm

Bk. Of E. Abut. 34+561.810

4 Poth

Timber Blocking, See "Timber Blocking Detail

2.438m (Typ.)

~ 2.00m

NOT TO SCALE

244.179

Timber Approach Handrail,

and "Bridge Details" Sheet

DESIGN LOADING Pedestrian/Bicycle = $4.07KN/m^2$ (85 psf) Vehicular = H-10

HIGHWAY CLASSIFICATION Functional Class: Multi-Use Path

DESIGN SPECIFICATIONS

2002 AASHTO "Standard Specifications for Highway Bridges" - 17th Edition 1997 AASHTO "Guide Specifications for Design of Pedestrian Bridges"

DESIGN STRESSES

FIELD UNITS
fc = 24 MPa (3,500 psi) - Cast-in-Place Concrete fy = 400 MPa (60,000 psi) - Reinforcement $f_V = 250 \text{ MPa } (36,000 \text{ psi}) - \text{Fasteners}$ fy = 250 MPa (36,000 psi) - Diaphragm Steel Fb = 5.9 MPa (850 psi) - Timber Stringers Fv = 0.7 MPa (100 psi) - Timber Stringers


Fb = 6.7 MPa (975 psi) - Timber Decking SEISMIC DATA

Seismic Performance Category (SPC) = A Bedrock Acceleration Coefficient (A) = 0.0325g Site Coefficient (s) = 1.0

See "General Notes Bridge" Sheet +0.558% 0.0% STRUCTURE LIMITS PROFILE GRADE

INDEX OF BRIDGE SHEETS

1. Bridge NO: 125 GP&E 2. Bridge Details 3. Bridge Details




BRIDGE 125 GENERAL NOTES

- 1. Refer to "BRIDGE GENERAL NOTES" Sheet for additional Timber Bridge GENERAL NOTES.
- 2. The Contractor shall remove all elements of the existing Timber Decking and properly dispose of it off-site. This includes: Transverse Railroad Ties, Timber Walkway, Steel Angle, Timber Bearing Supports, Excess Limestone Blocks, and any other items as applicable to the existing Timber Decking which is necessary to set new Timber Stringers. All items to be removed shall be disposed of in conformance with the requirements of Section 202.03 of the IDOT Standard
 Specifications. All material and labor necessary to complete this item of work shall be included in
 the Contract Unit Price for REMOVAL OF EXISTING SUPERSTRUCTURE with no additional
- 3. The Contractor shall remove any loose or deteriorated mortar from the existing masonry limestone abutment joints. He shall then clean and tuck point in accordance with the Contract Special Provisions. This work will be paid for as Lump Sum at the Contract Unit Price for MASONRY CLEANING AND TUCK POINTING.
- 4. All tree removal and selective brush clearing shall be in accordance with the Plans and Special Provisions or as directed by the Engineer. TREE REMOVAL and SELECTIVE CLEARING will be measured and paid for at the Contract Unit Price for the respective individual items.
- 5. The Contractor shall furnish and install a brass Name Plate in accordance with the Section 515 of the IDOT Standard Specifications except that it shall be installed with four (4) tamper resistant screws to the top timber bridge rail on the right hand side side of the approach end while looking in the direction of increasing Stationing. The plate shall be made of solid brass 3mm thick with imprinted stamp lettering 6mm high. This item will be measured and paid at the Contract Unit Price EACH for NAME PLATE.
- 6. Diaphragm Blocking and incidental hardware will not be paid separately, but shall be incidental to the TREATED TIMBER.
- 7. The intent of the Plan is to Reuse/Reset the existing Steel Stringers as an assembly after modifying the existing abutments. The assembly includes the existing Steel Stringers with the connected Diaphragms and Steel Bearings. The Contractor shall take the necessary precautions so as not to cause damage when removing the existing Steel Stringer Assemblies. The Contractor will be responsible for the repair or replacement of any item damaged, with no additional compensation allowed. The Contractor shall coordinate the schedule of this work with the Engineer to allow for detailed inspection of the Steel Stringer Assemblies if required. All material and labor necessary to complete this item of work shall be included in the Contract unit price for REMOVE AND RESET EXISTING STEEL STRINGER ASSEMBLIES and shall as one (1) unit per

TOTAL BILL OF MATERIALS

ITEM	UNITS	TOTAL
Remove and Reset Existing Steel Stringer Assembly	Each .	1
Removal of Existing Superstructure	Each	1
Concrete Structures	Cu. M.	4.13
Reinforcement Bars	Kg .	352
Treated Timber	Cu. M.	1.99
Hardware	Kg.	102
Wood Rail	Meter	9.75
Drill and Grout Bars	Each	114
Anchor Bolts, M20	Each	12
Masonry Cleaning and Tuckpointing	. L. Sum	1
Name Plate	Each	1 .
Monodirectional Prismatic Barrier Reflectors	Each	12
Porous Granular Embankment	Cu. M.	5
Structure Excavation	Cu. M.	5.3



Desie 17/14/11 80. Date 11/30/12

GENERAL PLAN & ELEVATION BRIDGE 125 OVER A MINOR DITCH TRIBUTARY TO THE PECATONICA RIVER WINNEBAGO COUNTY SECTION NO. 94-00267-00-BT STATION 34+560.26

LOCA	TION	SK	FTO	H

SHEET | OF 3

· ·	SHEET REVIEW	REVISIONS
	AGENCY DATE	NO. :TEM DATE

150mmx406mmx2,464m Treated Timbe

3.658m End-To-End Of Rail

Stringers (2)

PLAN

SCALE:	N/A	
DRAWN BY:	REK	
CHECKED: BY:	JWH	7282 Argus Orive (815) 398-2332
DATE:	DECEMBER 12, 2011	Design Firm Copyright 2011 By I

	McClure Engineering Associates, Inc.	
7282 Argus Drive (815) 398-2332 Design Firm Licens	Rockford, illinois 61107-5837 FAX (816) 398-2496 e: illinois 184-000816 Engineering Associates, Inc.	

		BRIDGE NO. 125 GP&E	
		PECATONICA PRAIRIE PATH WINNEBAGO COUNTY HIGHWAY DEPARTMENT SECTION 94-00267-00-BT	
5	İ	FILE:H:\I0-042 WINN CO PEC PATH\DESIGN\DRAWINGS\BRIDGES\I0-042 BI25.DWG J0B:04-30-I0-042	L

SHEET- NO. 96 107