

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SIDEWALK 20% VILLAGE 0021
542C5479	PIPE CULVERTS, CLASS C, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	12	12
* 54210189	PIPE ELBOW, 24"	EACH	1	1
54215769	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	1	1
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2	2
60108100	PIPE UNDERDRAINS, 4" (SPECIAL)	FOOT	247	247
60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5
67100100	MOBILIZATION	L SUM	1	1
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	144	144
X2010510	CLEARING AND GRUBBING	L SUM	1	1
* X5121800	PERMANENT STEEL SHEET PILING	SO FT	3,106	3,106
* X6640560	CHAIN LINK FENCE, 6' (SPECIAL)	FOOT	222	222
X7010216	TRAFFIC CONTROL AND PROTECTION SPECIAL	L SUM	1	1
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SO FT	208	208
* Z0055800	RUSTIC RAIL FENCE	FOOT	24	24

\* = SPECIALTY ITEM

FILE NAME = SHT-500.DGN	USER NAME = PAR	DESIGNED - BAJ	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>1ST STREET SIDEWALK SUMMARY OF QUANTITIES</b>		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - PAR	REVISED -		SCALE:	SHEET NO. 2 OF 2 SHEETS	STA. 7+63.74 TO STA. 23+59.93	10-00019-00-SW	ROCK ISLAND	40	4
		CHECKED - BAJ	REVISED -				<b>CONTRACT NO. 85555</b>				
		DATE - 01-13-12	REVISED -		ILLINOIS FED. AID PROJECT						