

EARTHWORK

LOCATION STA	20200100 EARTH EXCAVATION	EARTH EXCAV ADJ FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE (+) OVERAGE (-) SHORTAGE	20400800 FURNISHED EXCAVATION	WASTE	COMMENTS
	CUYD	CUYD	CUYD	CUYD	CUYD	CUYD	
1ST STREET							
7+63.74 TO 13+38.88	9	7	786	-779	779		
14+33.05 TO 17+98.83	7	5	287	-282	282		
19+05.03 TO 22+72.89	4	3	599	-596	596		
TOTALS	20	15	1,672	-1,657	1,657	0	

CROSSWALKS

LOCATION STA	44200944 CLASS B PATCHES TYPE IV, 8"	44213208 TIE BARS 1 1/4"	44213200 SAW CUTS FOOT	78001180 PAINT PAVEMENT MARKING, 24"	COMMENTS
	SQ YD	EACH	FOOT	FOOT	
W 6TH AVE	42	64	76	54	
W 5TH AVE	45	68	81	54	
W 4TH AVE			43	36	ALSO SEE DRIVEWAY SCHEDULE
TOTALS	87	132	200	144	

SEEDING / TEMPORARY EROSION CONTROL SEEDING

LOCATION STA	PERMANENT SEEDING			FERTILIZER NUTRIENTS			(NOTE 1)	
	25000100	25000300	25000300	25000400	25000500	25000600	28000250 TEMP EROS CONTR SEED	25100115 MULCH METHOD 2
	CL 1 ACRE	CL 2 ACRE	CL 3 ACRE	NITROGEN POUND	PHOSPHORUS POUND	POTASSIUM POUND	POUND	ACRE
1ST STREET								
7+63.74 TO 13+67	0.221		0.072	26	26	26	59	0.9
14+01 TO 18+33		0.088	0.038	11	11	11	25	0.4
18+67 TO 23+24		0.177	0.054	21	21	21	46	0.7
TOTALS	0.22	0.27	0.16	59	59	59	130	2.0

- NOTES:**
1. TEMPORARY SEEDING QUANTITY IS ESTIMATED AT 2 TIMES THE PERMANENT SEEDING ACREAGE.
 2. VERIFY PERMANENT AND TEMPORARY SEEDING AMOUNTS WITH ENGINEER PRIOR TO ORDERING MATERIALS.
 3. MULCH METHOD 2 QUANTITY IS ESTIMATED TO COVER ALL PERMANENT AND TEMPORARY SEEDING AREAS.
 4. NUTRIENTS NOT APPLIED TO TEMPORARY SEEDING.

ENTRANCES

LOCATION STA	DESCRIPTION	WIDTH FT	EXIST PAVT TYPE	TOTAL AREA (PROP) SQ YD	REMOVALS			COMMENTS
					44000200 DRIVEWAY PVMT REM	44004250 PAVED SHLD REM	42300300 PCC DRIVEWAY PVMT, 7"	
					SQ YD	SQ YD	SQ YD	
8+10	CE	32	HMA	174	160	29	174	CHURCH
23+40.17	SIDEROAD	22	SEALCOAT	62			62	W 4TH AVE; ALSO SEE CROSSWALK SCHEDULE
TOTALS					160	29	236	

TEMPORARY EROSION CONTROL SYSTEMS

LOCATION STA	SIDE	28000400 PERIMETER EROS BARRIER	28000500 INLET AND PIPE PROTECT	28100805 STONE DUMPED RIPRAP, CL A3	25100630 EROS CONTR BLANKET	28000305 TEMP DITCH CHECKS
		FOOT	EACH	TON	SQ YD	FOOT
1ST STREET						
8+67	RT		1			
9+29 TO 12+75	LT	344				
9+75 TO 12+00	LT				350	
14+75 TO 18+17	LT				184	
15+74	LT					25
16+79	LT					25
16+90 TO 17+08	LT			4		
19+00 TO 21+25	LT				262	
20+40 TO 22+84	LT	248				
TOTALS		592	1	4	796	50

SIDEWALKS

LOCATION STA	SIDEWALK REM SQ FT	44000600 PCC SIDEWALK 5"	42400200 DETECTABLE WARNINGS	COMMENTS
		SQ FT	SQ FT	
7+63.74 TO 7+90	129			
7+63.74 TO 13+67		3,008		
W 6TH AVE			16	2 LOCATIONS
14+01 TO 18+32		2,205		
W 5TH AVE			24	2 LOCATIONS
18+67 TO 23+25		2,444		
23+51 TO 23+60		36		
W 4TH AVE			16	2 LOCATIONS
TOTALS	129	7,693	56	