

SHORT-TERM PAVEMENT MARKING			
STATION TO STATION	CENTERLINE		STOP BAR
	SKIP DASH - YELLOW	SOLID - WHITE	
	4"	4"	
FOOT			
F.A.S. RTE. 258 (C.H. 2)			
37+78.29 TO 49+88.00	596.5	168.0	
50+12.00 TO 63+55.65	663.2	168.0	
TWO APPLICATIONS	2519.4	672.0	
USE	3192		
THESE QUANTITIES MAY NOT BE REQUIRED DEPENDING ON TIMING FOR STAGE 3.			

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS			
STATION	SIDE	OFFSET	EACH
F.A.S. RTE. 258 (C.H. 2)			
36+00.00	RT	35.13'	1
36+00.00	LT	34.87'	1
38+57.54	RT	45.00'	1
38+57.54	LT	50.00'	1
43+10.80	RT	45.00'	1
43+10.80	LT	50.00'	1
45+36.55	RT	50.00'	1
45+36.55	LT	45.00'	1
48+24.74	RT	50.00'	1
48+24.74	LT	45.00'	1
48+90.00	RT	50.00'	1
49+00.00	LT	60.00'	1
49+50.00	RT	100.00'	1
49+60.00	RT	150.00'	1
49+60.00	LT	100.00'	1
50+40.00	RT	100.00'	1
50+40.00	LT	150.00'	1
50+50.00	LT	100.00'	1
51+00.00	RT	60.00'	1
51+10.00	LT	50.00'	1
51+79.36	RT	45.00'	1
51+79.36	LT	50.00'	1
54+77.55	RT	45.00'	1
54+77.55	LT	50.00'	1
57+12.30	RT	50.00'	1
57+12.30	LT	45.00'	1
61+67.40	RT	50.00'	1
61+67.40	LT	45.00'	1
64+00.00	RT	35.12'	1
64+00.00	LT	34.88'	1
TOTAL			30

WORK ZONE PAVEMENT MARKING REMOVAL						
LOCATION	LINE					
	4"	6"	8"	12"	24"	
SQ FT						
F.A.S. RTE. 258 (C.H. 2)						
37+78.29 TO 49+88.00	1518		137	129	112	
50+12.00 TO 63+55.65	1709		137	129	112	
U.S. RTE. 52 (N. 38TH RD.)						
97+50.00 TO 102+50.00	136	75				
SUB-TOTAL						
	3363	75	274	258	224	
TOTAL						
	4194					

SEALING ABANDONED WATER WELLS				
STATION	SIDE	PARCEL NO.	PREVIOUS OWNER	EACH
F.A.S. RTE 258 (C.H. 2)				
42+82.0	1' LT	1	HUPP	1
TOTAL				1
USE				1

TEMPORARY PAVEMENT REMOVAL			
LOCATION			PAVEMENT REMOVAL
STATION TO STATION			SQ YD
F.A.S. RTE. 258 (C.H. 2)			
47+22.2 TO 49+88.0			326.5
50+12.0 TO 53+14.0			378.8
TOTAL			706

PIPE UNDERDRAINS					
STATION TO STATION	SIDE		PIPE UNDERDRAINS, 4"	PIPE UNDERDRAINS, 4" (SPECIAL)	CONCRETE HEADWALLS FOR PIPE DRAINS
			FOOT	FOOT	EACH
F.A.S. RTE. 258 (C.H. 2)					
39+00 TO 48+00	RT		900	36	3
44+00 TO 48+00	LT		400	24	2
51+00 TO 59+00	RT		800	36	3
51+00 TO 59+00	LT		800	36	3
TOTAL			2900	132	11

TEMPORARY PAVEMENT MARKING						
STATION TO STATION	LINES					
	4"		6"	8"	12"	24"
	SOLID WHITE	DOUBLE YELLOW	SKIP-DASH YELLOW	SOLID WHITE	SOLID WHITE	SOLID WHITE
EDGE OF PAVT.		CL	CL	LANE LINE	MED. / DIAG.	STOP BAR
FOOT						
F.A.S. RTE. 258 (C.H. 2)						
STAGE 2						
47+22.2 TO 49+88.0	542	678				11
50+12.0 TO 53+14.9	620	1026				11
STAGE 3						
37+78.29 TO 49+88.00	2739	2386				
50+12.00 TO 63+55.65	2817	2653				
SOUTHEAST ISLAND						
				205	129	28
NORTHWEST ISLAND						
				205	129	28
U.S. RTE. 52 (N. 38TH RD.)						
97+50.00 TO 102+50.00	407		150			
SUB TOTAL						
	7125	6743	150	410	258	78
TOTAL						
	13868		150	410	258	78

PAVEMENT MARKING								
STATION TO STATION			PAINT PAVEMENT MARKING				PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID	
			LINES					
			4"	6"	8"	12"	24"	
			SOLID WHITE	DOUBLE YELLOW	SKIP-DASH YELLOW	SOLID WHITE	SOLID WHITE	SOLID WHITE
			EDGE OF PAVT.	CL	CL	LANE LINE	MED. / DIAG.	STOP BAR
FOOT								
F.A.S. RTE. 258 (C.H. 2)								
37+78.29 TO 49+88.00	2739	2386						
50+12.00 TO 63+55.65	2817	2653						
SOUTHEAST ISLAND								
				205	129	28		
NORTHWEST ISLAND								
				205	129	28		
U.S. RTE. 52 (N. 38TH RD.)								
97+50.00 TO 102+50.00	407		150					
SUB TOTAL								
	5963	5039	150	410	258	56		
TOTAL								
	11002		150	410	258	56		

FILE NAME = v:\2844\2844q804.dgn

USER NAME = bdearene
 PLOT SCALE = 1/8" = 1' / IN.
 PLOT DATE = 12/21/2011

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

F.A.S. RTE. 258 (C.H. 2) & U.S. RTE. 52 (N. 38TH RD.)
 SCHEDULES OF QUANTITIES

SCALE: N/A SHEET NO. 3 OF 3 SHEETS STA. N/A TO STA. N/A

F.A.S. RTE. 258	SECTION 11-00325-00-SP	COUNTY LA SALLE	TOTAL SHEETS 84	SHEET NO. 16
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 87479	