

ITEM NUMBER	ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	387
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	196
20101100	TREE TRUNK PROTECTION	EACH	27
20200100	EARTH EXCAVATION	CU YD	21973
20800150	TRENCH BACKFILL	CU YD	1040
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	14867
25000210	SEEDING, CLASS 2A	ACRE	3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	277
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	277
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	277
25100115	MULCH, METHOD 2	ACRE	3
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	968
28000305	TEMPORARY DITCH CHECKS	FOOT	284
28000400	PERIMETER EROSION BARRIER	FOOT	4818
28000500	INLET AND PIPE PROTECTION	EACH	8
28000510	INLET FILTERS	EACH	57
28100107	STONE RIPRAP, CLASS A4	SQ YD	15
28200200	FILTER FABRIC	SQ YD	15
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	8294
35100100	AGGREGATE BASE COURSE, TYPE A	TON	223
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	8
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	94
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GAL	5966
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT-JOINT	SQ YD	20
40603100	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N30	TON	2496
40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	1324
42001300	PROTECTIVE COAT	SQ YD	3162
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	121
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	15392
42400800	DETECTABLE WARNINGS	SQ FT	40
44000100	PAVEMENT REMOVAL	SQ YD	1466
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	159
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	733
44000600	SIDEWALK REMOVAL	SQ FT	548
50105220	PIPE CULVERT REMOVAL	FOOT	171

ITEM NUMBER	ITEM	UNIT	QUANTITY
54213447	END SECTIONS, 12"	EACH	6
54213456	END SECTIONS, 21"	EACH	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	754
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	138
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	26
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1225
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	818
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	485
60218400	MANHOLES, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	2
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	2
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	5
60500060	REMOVING INLETS	EACH	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	5750
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	109
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	21
67100100	MOBILIZATION	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	18
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	30
* 78000100	THERMOPLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	109
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	910
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	42
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1273
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	145
78300100	PAVEMENT MARKING REMOVAL	SQ FT	875
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	627
X6024240	INLETS, SPECIAL	EACH	46
X6060160	COMBINATION CONCRETE CURB AND GUTTER OUTLET (SPECIAL)	EACH	2
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1
XX000856	MAILBOX REMOVAL AND RELOCATION	EACH	3
XX006498	COMBINATION CONCRETE CURB AND SIDEWALK 4 INCH (SPECIAL)	SQ FT	144
Z0034105	MATERIAL TRANSFER DEVICE	TON	1324
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Δ Z0076600	TRAINEES	HOURL	1000

Δ 0042
* SPECIALTY ITEMS



FILE NAME =	USER NAME = dws00878	DESIGNED - DLC	REVISED - -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
I:\08\Jobs\08L0212\CAD\Road\Sheet\c-601.dgn		DRAWN - DLC	REVISED - -		6698	10-00183-00-FP	TAZEWELL	81	3				
PLOT SCALE = 20.0000' / in.		CHECKED - MGD	REVISED - -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT M-5093 (154)	
PLOT DATE = 11/02/2011		DATE - 10/18/11	REVISED - -										