

EARTHWORK SUMMARY					
LOCATION	EARTH EXCAVATION Cubic Yard	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE Cubic Yard	EMBANKMENT Cubic Yard	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) Cubic Yard	UNSUITABLE MATERIAL
PETRI LANE					
STA. 17+00.00 TO STA. 18+14.57	12	9	0	9	0
STA. 23+55.00 TO STA. 53+50.00	5188	3891	4493	-602	0
OLD PETRI LANE					
STA. 500+76.00 TO STA. 501+58.44	95	71	9	62	0
14TH ST					
STA. 427+25.00 TO STA. 428+50.00	29	22	13	9	0
INFILTRATION BASIN					
	16650	12488	0	12488	0
TOTAL	21973	16481	4515	11966	0

EROSION CONTROL SCHEDULE										
LOCATION	TREE TRUNK PROTECTION	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	INLET FILTERS	TEMPORARY DITCH CHECK	TEMPORARY EROSION CONTROL SEEDING	STONE RIPRAP, CLASS A4	FILTER FABRIC		
									EACH	FOOT
BEGIN STATION	END STATION									
PETRI LANE										
13+79.49	18+14.57	0	204	0	3	0	3	0	0	
23+55.00	53+50.00	27	3455	5	51	284	202	0	0	
OLD PETRI LANE										
500+76.00	501+58.44	0	23	0	0	0	0	0	0	
14TH STREET										
422+86.67	429+36.65	0	0	2	3	0	0	0	0	
INFILTRATION BASIN										
		0	0	1	0	0	102	15	15	
STOCKPILE										
		0	1136	0	0	0	661	0	0	
TOTAL		27	4818	8	57	284	968	15	15	

DRIVEWAY SCHEDULE					
LOCATION	AGGREGATE BASE COURSE, TYPE A	PORTLAND CEMENT DRIVEWAY PAVEMENT, 6"	AGGREGATE SURFACE COURSE, TYPE A	AGGREGATE FOR TEMPORARY ACCESS	PROTECTIVE COAT
BEGIN STATION	END STATION				
PETRI LANE					
13+79.49	18+14.57	0	0	0	0
23+55.00	53+50.00	26	121	8	94
TOTAL		26	121	8	94

PAVEMENT AND CURB & GUTTER SCHEDULE										
LOCATION	SUB-BASE GRANULAR MATERIAL, TYPE A	AGGREGATE BASE COURSE, TYPE A	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N30	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N30	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER OUTLET, SPECIAL	PROTECTIVE COAT	MATERIAL TRANSFER DEVICE
BEGIN STATION	END STATION									
PETRI LANE										
13+79.49	18+14.57	0	0	0	0	38	0	0	9	0
23+55.00	53+50.00	8158	0	2451	1298	5860	5712	109	0	1305
OLD PETRI LANE										
500+76.00	501+58.44	136	0	45	26	106	0	0	2	0
TOTAL		8294	0	2496	1324	5966	5750	109	2	1314
FROM DRIVEWAY SCHEDULE										121
FROM SIDEWALK SCHEDULE										1727
TOTAL										3162

© Copyright Hanson Professional Services Inc. 2011
HANSON
 Hanson Professional Services Inc.

FILE NAME =	USER NAME = dawso00878	DESIGNED - DLC	REVISED -
I:\08Jobs\08L0212A\CAD\Road\Sheet\c-602sch.dgn		DRAWN - DLC	REVISED -
	PLOT SCALE = 20.0000' / 1"	CHECKED - MGD	REVISED -
	PLOT DATE = 09/14/2011	DATE - 9/14/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6698	10-00183-00-FP	TAZEWELL	81	8
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT M-5093 (154)				