

**AGGREGATE SCHEDULE**

LOCATION	AGG. BASE COURSE, TYPE A (TON)	AGG. SHOULDERS, TYPE A (TON)	BITUMINOUS MATERIALS (GALLON)
STA. 13+80 TO STA. 26+50	1260		618
STA. 26+50 TO STA. 36+82	1232		540
STA. 36+82 TO STA. 50+10	---	807	
STA. 50+10 TO STA. 52+50	---	91	
STA. 0+73 TO STA. 2+50 (CHAUTAUQUA ROAD)	84	26	44
F.E. STA. 21+79 RT.	---	61	
P.E. STA. 25+27 RT.	---	13	
P.E. STA. 29+23 RT.	---	24	
P.E. STA. 34+02 LT.	---	15	
P.E. STA. 34+53 RT.	---	17	
F.E. STA. 35+71 LT.	---	10	
P.E. STA. 40+77 RT.	---	20	
P.E. STA. 43+78.R RT.	---	8	
P.E. STA. 45+46 RT.	---	7	
F.E. STA. 46+80 LT.	---	11	
P.E. STA. 47+08 RT.	---	8	
P.E. STA. 49+45 RT.	---	8	
P.E. STA. 52+06 RT.	---	15	
TOTAL	2576	1141	1202

**EARTHWORK SCHEDULE**

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 13+55 TO STA. 26+50	548	411	15159	-14748
STA. 26+50 TO STA. 40+00	1101	825	3844	-3018
STA. 40+00 TO STA. 52+50	571	428	3300	-2872
STA. 0+20 TO STA. 2+50 (CHAUTAUQUA ROAD)	183	137	545	-408
TOTAL	2403	1802	22848	21046

**HOT MIX ASPHALT SCHEDULE**

LOCATION	HMA BINDER COURSE IL-19.0 N50 (TON)	HMA SURF. COURSE MIX C N50 (TON)	BIT. MATERIALS (PRIME COAT) (TON)	AGGREGATE PRIME COAT (TON)	HMA BASE CSE. WIDE. 6" (SQ. YD.)
STA. 13+80 TO STA. 36+82	2785	1155	3.89	20.46	
STA. 36+82 TO STA. 52+50	153	475	1.59	8.36	967
STA. 0+20 TO STA. 2+50 (CHAUTAUQUA ROAD)	441	60	0.02	0.11	137
TOTAL	3379	1690	5.50	28.93	1104

**SCHEDULE PIPE CULVERTS, CLASS D, TYPE 1 & METAL END SECTIONS**

LOCATION	PIPE CULVERTS (FOOT)		METAL END SECTIONS (EACH)	
	15"Ø	18"Ø	15"	18"
STA. 33+88 TO STA. 34+28 LT.	40		2	
STA. 43+66 TO STA. 44+00 RT.	34		2	
STA. 45+29 TO STA. 45+63 RT.	34		2	
STA. 49+29 TO STA. 49+61 RT.	32		2	
STA. 29+13 TO STA. 29+77 RT.		56		1
STA. 34+62 TO STA. 34+94 RT.		32		2
STA. 40+51 TO STA. 40+97 RT.		46		2
STA. 51+87 TO STA. 52+27		40		2
STA. 1+70 TO STA. 2+10 (CHAUTAUQUA RD.)		40		2
TOTAL	140	214	8	9

**SCHEDULE PAINT PAVEMENT MARKING LINE - 4"**

LOCATION	WHITE SOLID (FOOT)	YELLOW SOLID (FOOT)	YELLOW 10' STRIPE 30' SKIP DASH (FOOT)
STA. 0+20 TO STA. 2+50 (CHAUTAUQUA RD.)	486	230	60
STA. 13+55 TO STA. 52+50	7670	7790	
SUB-TOTAL	8156		8080
TOTAL		16236	

**SCHEDULE HOT MIX ASPHALT SURFACE REMOVAL-BUTT JOINT**

LOCATION	QUANTITY (SQ. YD.)
STA. 13+80 TO STA. 14+91.8	274
STA. 2+20.7 TO STA. 2+50 (CHAUTAUQUA RD.)	65
TOTAL	339

**SCHEDULE GUARDRAIL REMOVAL**

LOCATION	QUANTITY (FOOT)
STA. 13+64.5 TO STA. 15+11.5	147
STA. 13+73 TO STA. 16+20	247
TOTAL	394

**SCHEDULE FURNISHING AND ERECTING RIGHT OF WAY MARKERS**

LOCATION	QUANTITY (EACH)
STA. 13+60 50.07' LT. & 80' LT.	2
STA. 13+60 44.96' RT. & 80' RT.	2
STA. 17+00 80' LT.	1
STA. 17+45 90' LT.	1
STA. 2+50 30.6' RT. (CHAUTAUQUA RD.)	1
STA. 1+88.33 50' LT. (CHAUTAUQUA RD.)	1
STA. 19+00 80' LT.	1
STA. 22+00 75' LT.	1
STA. 22+50 80' RT.	1
STA. 24+00 60' RT.	1
STA. 24+41.71 47.31' LT.	1
STA. 25+12.30 60' RT.	1
STA. 25+12.30 40.86' RT.	1
STA. 27+93.04 60' LT.	1
STA. 31+75.87 60' LT.	1
STA. 33+97.44 60' LT.	1
STA. 34+27.11 50' LT.	1
STA. 37+23.83 46.7' LT. & 50' LT.	2
STA. 38+50 85' RT.	1
STA. 39+50 85' RT.	1
STA. 40+00 60' RT.	1
STA. 40+50 50' LT.	1
STA. 41+00 80' LT.	1
STA. 42+00 80' LT.	1
STA. 43+00 60' RT.	1
STA. 43+00 50' RT.	1
STA. 44+00 45' LT.	1
STA. 46+41.98 45' LT. & 50' RT.	2
STA. 47+12.40 45' LT.	1
STA. 47+12.40 55' LT.	1
STA. 51+23.87 50' RT.	1
STA. 51+23.96 44.61' RT.	1
STA. 51+87.42 55' LT.	1
TOTAL	37

**SCHEDULE RELOCATE EXISTING MAILBOX**

LOCATION	QUANTITY (EACH)
STA. 25+14 24' RT. TO STA. 25+14 25' RT.	2
STA. 29+50 20' RT. TO STA. 29+65 25' RT.	1
STA. 34+53 23' RT. TO STA. 34+55 25' RT.	1
STA. 40+90 22' RT. TO STA. 40+99 25' RT.	1
STA. 43+97 17' RT. TO STA. 44+06 25' RT.	1
STA. 45+62 15' RT. TO STA. 45+68 25' RT.	1
STA. 47+26 19' RT. TO STA. 47+32 25' RT.	1
STA. 49+58 20' RT. TO STA. 49+66 25' RT.	1
STA. 52+19 21' RT. TO STA. 52+30 15' RT.	1
TOTAL	10

**SCHEDULE PIPE CULVERT REMOVAL**

LOCATION	QUANTITY (FOOT)
STA. 16+01 - 14' LT. TO 50' LT. 12"Ø CMP	40
STA. 0+91 (CHAUTAUQUA RD.) - 30"Ø CMP	50
STA. 29+10 TO STA. 29+58 RT. - 15"Ø CMP	46
STA. 33+79 TO STA. 34+29 LT. - 18"Ø CMP	50
STA. 34+40 TO STA. 34+84 RT. - 18"Ø CMP	44
STA. 44+66 TO STA. 44+98 RT. - 15"Ø CMP	32
STA. 45+32 TO STA. 45+62 RT. - 15"Ø CMP	32
STA. 46+93 TO STA. 47+25 RT. - 15"Ø CMP	32
STA. 49+30 TO STA. 49+62 RT. - 15"Ø CMP	32
STA. 51+91 TO STA. 52+24 RT. - 15"Ø CMP	34
TOTAL	392

**SCHEDULE SEEDING, CLASS 2 (SPECIAL) & TEMPORARY EROSION CONTROL SEEDING**

LOCATION	QUANTITY (ACRE)	TEMP. EROS. CONTROL SEED (POUND)
STA. 13+60 TO STA. 52+50 LT. (C.H. 2)	3.21	289
STA. 13+60 TO STA. 52+50 RT. (C.H. 2)	3.33	300
STA. 0+80 TO STA. 2+50 (CHAUTAUQUA RD.)	0.34	31
TOTAL	6.88	620

**SCHEDULE FENCE REMOVAL**

LOCATION	QUANTITY (FOOT)
STA. 27+18 TO STA. 33+75 LT.	657
STA. 38+12 TO STA. 39+47 RT.	192
STA. 38+50 TO STA. 52+50 LT.	1398
TOTAL	2247

**SCHEDULE PAVEMENT REMOVAL**

LOCATION	QUANTITY (SQ. YD.)
STA. 13+80 TO STA. 26+00	136
STA. 26+00 TO STA. 28+00	489
STA. 28+00 TO STA. 43+00	167
STA. 43+00 TO STA. 47+10	489
STA. 47+10 TO STA. 52+50	60
STA. 0+73 TO STA. 1+08 (CHAUTAUQUA RD.)	78
TOTAL	1419

**SCHEDULE PIPE CULVERTS, CLASS A, TYPE 2 36"**

LOCATION	QUANTITY (FOOT)
STA. 0+91 (CHAUTAUQUA RD.)	86
TOTAL	86

**SCHEDULE PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"**

LOCATION	QUANTITY (EACH)
STA. 0+91 (CHAUTAUQUA RD.) 48' LT. & 38' RT.	2
TOTAL	2

**SCHEDULE PERIMETER EROSION BARRIER**

LOCATION	QUANTITY (FOOT)
STA. 13+60 80' RT. TO STA. 21+60 160' RT.	780
STA. 22+30 160' RT. TO STA. 25+25 60' RT.	410
STA. 25+60 60' RT. TO STA. 29+30 110' RT.	465
STA. 29+85 80' RT. TO STA. 34+35 45' RT.	485
STA. 35+00 45' RT. TO STA. 36+95 45' RT.	195
STA. 37+24 46' RT. TO STA. 40+50 85' RT.	372
STA. 41+00 85' RT. TO STA. 43+65 50' RT.	310
STA. 44+00 50' RT. TO STA. 45+30 50' RT.	130
STA. 45+60 50' RT. TO STA. 46+90 50' RT.	140
STA. 47+30 50' RT. TO STA. 49+30 50' RT.	200
STA. 49+60 50' RT. TO STA. 51+90 42' RT.	235
STA. 52+20 42' RT. TO STA. 52+50 42' RT.	30
STA. 13+60 80' LT. TO STA. 2+50 30' LT. (CHAUTAUQUA RD.)	543
STA. 2+50 29' RT. (CHAUTAUQUA RD.) TO STA. 33+80 60' LT.	1663
STA. 34+34 50' LT. TO STA. 35+55 50' LT.	121
STA. 35+85 50' LT. TO STA. 46+65 45' LT.	991
STA. 46+95 45' LT. TO STA. 52+50 55' LT.	565
TOTAL	7635