

GUARDRAIL SCHEDULE

LOCATION	T.B.T. TYPE 6 (EACH)	S.P.B.G.R. TYPE A (FOOT)	T.B.T. TYPE 1 SPECIAL (TANGENT) (EACH)	TERMINAL MARKER DIRECT APPLIED (EACH)
STA. 13+64 TO STA. 14+07.65 RT.	1			
STA. 14+07.65 TO STA. 15+45.15 RT.		137.5		
STA. 15+45.15 TO STA. 15+95.15 RT.			1	1
STA. 13+73 TO STA. 14+16.15 LT.	1			
STA. 14+16.15 TO STA. 16+28.65 LT.		212.5		
STA. 16+28.65 TO STA. 16+78.65 LT.			1	1
TOTAL	2	350	2	2

SCHEDULE TEMPORARY DITCH CHECKS

LOCATION	QUANTITY (FOOT)
STA. 19+50 71' LT.	8
STA. 25+50 31' LT.	8
STA. 27+00 33' LT.	8
STA. 28+50 33' LT.	8
STA. 30+00 36' LT & 33' RT.	16
STA. 31+50 30' LT & 35' RT.	16
STA. 33+50 30' LT. & 34' RT.	16
STA. 41+50 48' RT.	8
STA. 44+00 34' RT.	8
TOTAL	96

SCHEDULE CLASS SI CONCRETE (OUTLET)

LOCATION	QUANTITY (CU. YD.)
F.E. STA. 21+79 RT.	5.39
P.E. STA. 25+27.5 RT.	4.99
P.E. STA. 29+29 RT.	4.59
P.E. STA. 34+02 LT.	8.19
P.E. STA. 34+53 RT.	4.59
INLET - STA. 36+68 TO STA. 36+80 RT.	0.93
INLET - STA. 36+80 TO STA. 36+92 LT.	0.93
TOTAL	29.61

SAY 29.7 CU. YD.

SCHEDULE CONCRETE GUTTER TYPE A

LOCATION	QUANTITY (FOOT)
STA. 16+45 TO STA. 36+80 RT.	2035
STA. 18+90 TO STA. 36+80 LT.	1790
TOTAL	3825

SCHEDULE PIPE DRAINS 15"

LOCATION	QUANTITY (SQ. YD.)
STA. 16+50 25' TO 65' RT.	40
STA. 19+85 25' TO 62' LT.	36
TOTAL	76

SCHEDULE WOOD FENCE TO BE REMOVED AND RE-ERECTED

LOCATION	QUANTITY (FOOT)
STA. 33+84 TO STA. 33+88 LT.	24
STA. 34+09 TO STA. 34+25 LT.	22
TOTAL	46

SCHEDULE CLASS SI CONCRETE (OUTLET) SPECIAL *

LOCATION	QUANTITY (CU. YD.)
STA. 16+50 24' RT.	3.3
STA. 18+95 24' LT.	3.3
TOTAL	6.6

* STANDARD 606111

SCHEDULE CATCH BASINS, TYPE C, TYPE 8 GRATE

LOCATION	QUANTITY (EACH)
STA. 29+70 32' RT.	1
TOTAL	1

SCHEDULE GRATES AND COVERS, TYPE 2A

LOCATION	QUANTITY (EACH)
STA. 16+50 24' RT.	1
STA. 19+85 24' RT.	1
TOTAL	2

SCHEDULE WATER METER TO BE ADJUSTED

LOCATION	QUANTITY (EACH)
STA. 18+66 41' LT.	1
STA. 34+72 55' RT.	1
STA. 34+75 59' RT.	1
STA. 41+02 49' RT.	1
TOTAL	4

SCHEDULE FIRE HYDRANTS TO BE ADJUSTED

LOCATION	QUANTITY (EACH)
STA. 18+43 59' RT.	1
TOTAL	1

SCHEDULE TREE REMOVAL, ACRES

LOCATION	QUANTITY (ACRE)
STA. 13+60 29, 80' TO STA. 18+10 26, 60' RT.	0.61
STA. 13+60 28, 80' TO STA. 17+55 30, 44' LT.	0.35
STA. 21+77 30, 60' TO STA. 25+28 39, 47' LT.	0.20
STA. 22+00 24, 40' TO STA. 25+18 60' RT.	0.27
STA. 37+24 26, 47' TO STA. 39+73 32, 38' RT.	0.12
STA. 38+11 44, 60' TO STA. 52+50 27, 46' LT.	0.70
STA. 31+34 26, 47' TO STA. 33+76 31, 38' LT.	0.06
TOTAL	2.31

SAY 2.4 ACRE

SCHEDULE TREE REMOVAL

LOCATION	6 TO 15 UNITS DIA. (EACH)	OVER 15 UNITS DIA. (EACH)
STA. 20+48 42' RT.	18	
STA. 20+75 40' LT.		36
STA. 20+82 48' LT.		18
STA. 36+15 36' RT.	12	
TOTAL	30	54

SCHEDULE SIGN TO BE RELOCATED

LOCATION	QUANTITY (EACH)
STA. 19+10 69' LT.	1
STA. 29+75 52' LT.	1
TOTAL	2

SCHEDULE PLUG EXISTING CULVERTS

LOCATION	QUANTITY (EACH)
STA. 38+96 CROSS ROAD CULVERT	1
TOTAL	1

SCHEDULE HOT MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH

LOCATION	QUANTITY (SQ. YD.)
STA. 23+25 TO STA. 30+64	853
STA. 35+94 TO STA. 40+25	1054
STA. 44+20 TO STA. 52+50	2029
TOTAL	3936

SCHEDULE AGGREGATE DITCH

LOCATION	QUANTITY (TON)
STA. 25+50 TO STA. 33+88 LT.	432
STA. 29+71 TO STA. 32+50 RT.	81
STA. 34+16 TO STA. 34+50 LT.	18
TOTAL	531

SCHEDULE HEAVY DUTY EROSION CONTROL BLANKET

LOCATION	QUANTITY (SQ. YD.)
STA. 18+70 105' LT. TO STA. 20+50 76' LT.	332
TOTAL	332