N

20' 0 20' 40'
SCALE: 1" = 20'

SECTION 09-00016-00-SW
ELEMENTARY SCHOOL BEGINS
STA. 60+30.81

SAW CUT 12 FOOT OF WOOD POLE BEING USED AS PARKING EDGE TREATMENT AND REMOVE. COST SHALL BE INCLUDED IN COST OF EARTH EXCAVATION.

STA. 63+12.25 - 38° 39' SKEW RT. AHD.
45 FOOT, P CUL. CL D, TY 1, 18"
USFL 668.19, STA. 63+28.50, 13' RT
DSFL 668.04, STA. 62+93.50, 15' LT

BIT PATCH MATERIAL
2.0 TON

SECTION 09-00016-00-SW
ELEMENTARY SCHOOL ENDS
STA. 64+43.00

REMOVE STEEL BOLLARD.
COST SHALL BE INCLUDED
IN COST OF EARTH EXCAVATION.

PR PCC SWK, 6 INCH
125 SF

PI STA. 63+89.00

REM EX GRAV SURF.
PLACE EARTH FILL
(SEE X-SEC)

PR TEMP. CONST. ESMT. LINE

CONST. LIMITS

AGG SURF CRSE, TY B
4.5 TON

PR PCC SWK, 4 INCH
1936 SF

+66.81
2.50' LT

+66.81
2.50' RT

+83.19
2.50' LT

+83.19
2.50' RT

PI STA. 62+75.00

BM-2126-3 - "O" IN OPEN, TOP OF FH, N. SIDE OF FORTUNE STREET, 140'± W. OF ELEMENTARY SCHOOL ENTRANCE. ELEV - 674.46

BM-2126-3

PROPOSED PROFILE GRADE LINE
ALONG CL OF SIDEWALK

EXISTING GROUND LINE

VPI STA. 60+50.00
ELEVATION 671.37
EX PROF EL
PR BK SW PROF EL

VPI STA. 61+00.00
ELEVATION 671.37

VPI STA. 62+40.00
ELEVATION 671.60

VPI STA. 62+90.00
ELEVATION 671.42

VPI STA. 63+90.00
ELEVATION 669.97

VPI STA. 64+16.00
ELEVATION 670.14

671.03
+1.23%
+0.00%
+0.23%
-0.20%
-0.20%
-1.45%
+0.65%
-0.63%
669.97

680 675 670 665 660 655

60+00 60+50 61+00 61+50 62+00 62+50 63+00 63+50 64+00 64+50

670.95
671.28 671.37
671.21 671.37
671.25 671.49
671.44 671.60
671.40 671.50
670.07 671.28
669.21 670.55
669.93 670.04
669.93

FILE NAME = P:\09E2126\Design\Design\CADD Sheets\D6815-sht-plnprf-school.dgn	USER NAME = default	DESIGNED -	REVISED -
		DRAWN - MGM	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED - WJS	REVISED -
	PLOT DATE = 11/28/2011	DATE - 08/2011	REVISED -

CITY OF VIRDEN
SAFE ROUTES TO SCHOOLS PROGRAM

PLAN AND PROFILE
ELEMENTARY SCHOOL

SCALE: 1" = 20' | SHEET NO. OF SHEETS | STA. 60+00.00 TO STA. 65+00.00

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	09-00016-00-SW	MACOUPIN	31	15
		CONTRACT NO.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	SRTS-4009(047)	

93560