SUMMARY OF QUANTITIES

	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0031		
					0021	ITEP	
					100% LOCAL	80% FED. 20% LOCAL	50% FED. 50% LOCAL
	20200100	EARTH EXCAVATION	CU YD	160		160	
	20800150	TRENCH BACKFILL	CU YD	363		363	
	21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	1,458		1,458	
	25000200	SEEDING, CLASS 2	ACRE	0.3		0.3	
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27		27	
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27		27	
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27		27	
	25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.6		0.6	
	25100105	MULCH, METHOD 1	ACRE	0.3		0.3	
	28000510	INLET FILTERS	EACH	48		48	
	31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	935		935	
	42000300	PORTLAND CEMENT CONCRETE PAVEMENT, 8"	SQ YD	474		474	
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	935		935	
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	36,518		36,518	
	42400800	DETECTABLE WARNINGS	SQ FT	831		831	
	44000100	PAVEMENT REMOVAL	SQ YD	3,202		3,202	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	754		754	
	44000300	CURB REMOVAL	FOOT	3,223	1,556	1,667	
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,186	776	410	
	44000600	SIDEWALK REMOVAL	SQ FT	43,580		43,580	
	44200089	PAVEMENT PATCHING, TYPE I, 8 INCH	SQ YD	7		7	
	44200094	PAVEMENT PATCHING, TYPE II, 8 INCH	SQ YD	16		16	
	550B0030	STORM SEWERS, CLASS B, TYPE I 8"	FOOT	30		30	
	550B0040	STORM SEWERS, CLASS B, TYPE I 10"	FOOT	59		59	
	550B0050	STORM SEWERS, CLASS B, TYPE I 12"	FOOT	44		44	
Δ	56400100	FIRE HYDRANTS TO BE MOVED	EACH	3		3	
Δ	56400300*	FIRE HYDRANTS TO BE ADJUSTED	EACH	4		4	
	59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	18		18	
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1		1	
	60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	23		23	
	60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1		1	
	60266600*	VALVE BOXES TO BE ADJUSTED	EACH	15		15	

* SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES

	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0031		
					0021	ITEP	
					100% LOCAL	80% FED. 20% LOCAL	50% FED. 50% LOCAL
	60300305	FRAME AND LIDS TO BE ADJUSTED	EACH	3		3	
	60500060	REMOVING INLETS	EACH	21		21	
	60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	2		2	
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	364		364	
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	7,276	2,682	4,594	
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	111	107	4	
	60609800	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.18	FOOT	15	15		
	67100100	MOBILIZATION	L SUM	1		1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1	
	72000100	SIGN PANEL - TYPE 1	SQ FT	265		265	
	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	10		10	
	78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	19	19		
Δ	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	6,123	6,123		
Δ	78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	2,290	2,290		
Δ	78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	2,461	2,461		
Δ	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	372	372		
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,325	1,325		
Δ	81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	5,915		3,153	2,762
Δ	81028750	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA.	FOOT	460		95	365
Δ	81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	12		5	7
Δ	81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	12,310		4,094	8,216
Δ	81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	16,515		13,926	2,589
Δ	81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	13,590		10,159	3,431
Δ	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	8,440		6,672	1,768
Δ	81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	11,930		10,130	1,800
Δ	81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	10,915		10,915	
Δ	84200804	REMOVAL OF POLE FOUNDATION	EACH	34		34	
+	20076600	TRAINEES	HOUR	500			

* SEE SPECIAL PROVISIONS

\+ 0042 Δ SPECIALTY ITEMS

NOV 28, 2011 8:35 PM DFORGY
E:\JOBS\07L1101 LITCHFIELD STREETSCAPE\CADD\SUM_QUANTITIES.DWG

Prairie Engineers of Illinois, P.C.
200 S. Chicago St.
Lincoln, IL 62656
(217) 651-8017
www.prairieengineers.com
professional design firm no. 184-005965

© Copyright Prairie Engineers of Illinois, P.C. 2011

DRAWING DATE	11/29/11	REVISION	BY / DATE
DESIGNED BY	DEF		
DRAWN BY	TLW		
CHECKED BY	LDK 10/11		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CITY OF LITCHFIELD - DOWNTOWN STREETSCAPE PHASE 2

SUMMARY OF QUANTITIES

STATION TO STATION

PEI PROJECT NO.	07L1101
PAGE 3 OF 92 PAGES	
FILENAME	Sum_Quantities.dwg
DRAWING SCALE	NO SCALE

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00035-00-LS	Montgomery	92	3
		CONTRACT NO. 93563		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		